

24

Vital Pulp Therapy

GEORGE BOGEN, TILL DAMMASCHKE, and NICHOLAS CHANDLER

CHAPTER OUTLINE

The Living Pulp

Loss of Pulp Vitality

Pulpal Response to Caries

Dentin Regeneration and Reparative Tissue Formation

Tertiary Dentin Formation

Mineralized Tissue Formation After Loss of the Primary Odontoblasts

Indications for Vital Pulp Therapy

Procedures Generating Mineralized Tissue Barriers

Indirect Pulp Capping

Direct Pulp Capping

Partial Pulpotomy

Complete Pulpotomy

Materials for Vital Pulp Therapy

Aqueous Calcium Hydroxide Suspensions

Hard Setting Calcium Hydroxide Cements

Light-Curing Liners and Cements

Composite Resins, Dentin Adhesives, and Resin-Modified Glass Ionomer Cements

Mineral Trioxide Aggregate

Calcium Silicate Cements

Calcium Silicate Cement Applications in Vital Pulp Therapy

Direct Pulp Capping With Calcium Silicate Cements

Pulpotomy With Calcium Silicate Cements

Vital Pulp Therapy Techniques

Diagnosis

Caries Removal

Hemostatic Agents

Treatment Considerations

Treatment Recommendations

Pulp Capping and Pulpotomy

The Permanent Restoration

Postoperative Follow-Up and Recall

Acknowledgement

"There is nothing permanent except change."

—*Heraclitus*

Vital pulp therapy aims to preserve and maintain pulpal health in teeth challenged by trauma, caries, restorative procedures, and anatomic anomalies. The treatment can be completed for permanent teeth that show reversible pulpal injuries, and outcomes depend on several factors.^{87,192,252} The primary objective is to initiate the formation of new mineralized tissue. This procedure is essential for the preservation of involved immature permanent teeth where root development is incomplete, and maintenance of arch integrity is critical during maxillofacial development.⁷³

From the first description of direct pulp capping using gold foil by Philipp Pfaff in 1756, dentistry has recognized the ability of the injured pulp to repair.³⁰⁸ New materials now provide superior sealing properties to protect the pulp from microorganisms and their toxic by-products. Mineral trioxide aggregate (MTA) and other hydraulic calcium silicate cements (CSCs) partnered with advanced treatment strategies have changed the long-held concept that pulp capping after carious exposure should be avoided. The perception that outcomes for direct pulp capping in a carious field are inconsistent is based on traditional protocols and materials that did not generate a favorable environment for hard tissue formation.^{168,229,271,382} This has encouraged clinicians towards alternative treatments, such as pulpotomy or pulpectomy, particularly in immature permanent teeth.^{74,396} This is

further complicated by diagnostic difficulties, because clinical signs, symptoms, and radiographs may not accurately reflect the histologic condition of the pulp (Fig. 24.1).¹⁹⁶ However, based on a better understanding of pulp physiology, caries microbiology, and the inflammatory mechanisms responsible for irreversible changes, teeth with the potential for repair and continued vitality can now be more readily identified and predictably treated.⁵⁴

Maintaining pulp vitality is in contrast to root canal treatment where remaining pulp tissue is removed and the canal system shaped, disinfected, and obturated using root canal filling materials. Although success rates of over 90% can be achieved after approximately 5 years with careful treatment after vital extirpation the complete loss of function of the pulp tissue occurs, which can be disadvantageous.²¹ Proprioceptive protection is partially lost after orthograde treatment, permitting more than double the normal occlusal load before a provoked neuromuscular response occurs.^{32,314} This proprioceptive deficit can threaten long-term tooth function and survival. In contrast, vital tooth therapy provides a conservative option that exploits bioactive materials and strategies to save the dentition.

This chapter describes the microbiology of caries and the associated physiologic reactivity of pulp tissue. Understanding that pulp tissue has an innate potential for repair in the absence of bacterial contamination, new treatments in vital pulp therapy for the preservation of the pulpally involved permanent tooth are discussed.^{97,201}




Fig. 24.1 Radiographs of carious molars in patients aged 12 to 38 years. **A**, Mandibular left first molar in a 23-year-old with minor symptoms. **B**, Asymptomatic maxillary right second molar in a 16-year-old. **C**, Asymptomatic maxillary left first molar in a 38-year-old. **D**, Deep caries in the mandibular right first molar of a 12-year-old. All patients were referred to the endodontist for root canal treatment based on radiographic appearance. They exhibited normal vitality with cold testing, and all were treated successfully with vital pulp therapy. (© Dr. George Bogen.)

The Living Pulp

Vital pulp tissue comprises cells including fibroblasts, undifferentiated mesenchymal cells, odontoblasts, macrophages, dendritic cells, and other immunocompetent cells. The cells of the subodontoblastic layer and odontoblasts form a thin border between the dentin and the periphery of the pulp known as the *Höhl cell layer*.^{106,158} The odontoblasts are elongated columnar-shaped cells separated from the mineralized dentin by predentin and characterized by processes that extend into the dentin and possibly to the dentinoenamel junction.^{167,348,372,403} Odontoblasts form the mineralized predentin-dentin matrix, which includes phosphoproteins, glycoproteins, proteoglycans, and sialoproteins.²²⁰ Repair mechanisms in the pulp are similar to those in normal connective tissue injured by trauma. When the enamel and dentin are challenged and the pulp is exposed to advancing microorganisms, inflammatory changes can induce pulp necrosis, which precedes problems including infection and its complications.^{50,61} The pulp undergoes physiologic, pathologic, and defensive changes during its life.^{240,276,381} These include continued dentin apposition, causing reduction of coronal pulp volume and circumference and canal lumen dimensions.^{125,277} Atrophy results in fibrosis, dystrophic calcification, degeneration of odontoblasts, and increased cellular apoptosis.^{46,125} Aging of human pulp cells is primarily characterized by the formation of reactive oxygen species and senescence-related beta (β)-galactosidase activity.²³³ Pain sensitivity is reduced due to a decrease in fast-conducting A- δ fibers and diminished pulp repair, partly attributed to decreases in the levels of substances such as alkaline phosphatase.^{254,345}

A comparison analysis of gene expression levels reflecting cell function, proliferation, differentiation, and development found them markedly higher in young pulps.³⁸¹ Young dental pulps show greater cell and tissue differentiation, proliferation, and development of the lymphatic, hematologic, and immune systems compared to older pulps where the apoptosis pathway is highly expressed.³⁸¹ Although A- β fiber function remains constant with aging, a decrease in A- δ fibers with age may reduce the perception of pain by these fibers.²⁵⁴

In summary, the main functions of the dental pulp include dentin formation during development and life of the tooth, the transmission of stimuli via proprio- and pain receptors, and immune responses. The pulp also produces reparative dentin as a defense mechanism against external stimuli, and tissue during the formation and closure of the root apex.

Loss of Pulp Vitality

Pulpless teeth with minimal remaining tooth structure that undergo root-canal-filling procedures and are heavily restored become more vulnerable to irreparable fracture because of the loss of proprioceptive mechanisms.^{32,262,314,358} Moisture depletion from dentin and reduction of tooth stiffness are minimal after root canal treatment.^{186,204,241} Although root canal treatment can prolong tooth survival, the cumulative loss of tooth structure from endodontic and restorative treatment weakens teeth.^{64,76,118,393} Changes in root canal geometry are inevitable in the course of canal preparation and may lead to a higher incidence of fractures.^{151,235}

Other potential problems are tooth discoloration and increased caries risk because of plaque accumulation and altered microflora or due to the absence of the defenses of the pulp-dentin complex.^{224,263} Root-canal-filled teeth demonstrate an increased susceptibility to recurrent caries because of poor marginal integrity of restorations or modification of their biologic environment.^{78,263} Root canal treatments may be more complex than initially thought, while procedures for maintaining vitality are conservative, easy to implement, and often cost-effective.^{198,339}

Pulpal Response to Caries^a

The microbial advance in carious lesions is the primary cause of pulpal inflammation and potential necrosis. Acidogenic gram-positive bacteria, predominately oral streptococci and lactobacilli, produce lactic acid as the main metabolic by-product in active lesions that demineralizes enamel and dentin.^{136,176} Immune responses and inflammation occur when the caries front is within 1.5 mm of the pulp and bacterial antigens and metabolites diffuse through dentinal tubules.^{43,136,203,293} If bacterial challenge continues, immune cell responses lead to increased inflammation and edema, initially characterized clinically by pulpal pain. In the low-compliance environment of the pulp space, inflammation eventually leads to pulp disintegration and apical pathosis.^{176,376}

Advancing caries is initially confronted by protective innate immune responses, progressing to an adaptive response when bacteria directly approach the pulp.¹⁷⁵ The pioneer microbes first encounter a positive outward flow of dentinal fluid, characterized by the deposition of immunoglobulins and serum proteins that slow the diffusion of antigens.¹⁷⁶ Potent microbial metabolites, such as lipoteichoic acid and lipopolysaccharide, also activate the innate immune system. The by-products stimulate signaling by Toll-like receptors in odontoblasts when these cells first encounter the carious front. They also stimulate proinflammatory cytokines, including interleukin-1, interleukin-8, interleukin-12, tumor necrosis factor alpha, vascular endothelial growth factor (VEGF), and transforming growth factor beta (TGF- β).^{137,187,411} VEGF promotes vascular permeability and angiogenesis. Dentin mineralization and matrix metalloproteinase secretion are also induced by the increased expression of TGF- β . Cariogenic bacteria also activate complement pathways and induce the proinflammatory cytokine interferon γ , responsible for killing phagocytosed bacteria by activated macrophages.¹⁹⁰ Odontoblasts also participate in the adaptive response by the synthesis of reactionary dentin, which features diminished tubularity.⁸⁶ As microorganisms advance, the modified helical structure in reparative dentin constricts lumen diameter, forming a barrier against pathogens.⁸⁵

As pulpitis progresses, vasoactive neuropeptides contribute to increased vascular permeability and intrapulpal blood flow. Increases in neuropeptide concentration and nerve sprouting characterize neurogenic inflammation, which can cause a transient increase in interstitial tissue pressure and contribute to painful pulpitis.^{65,323} Immune cells

attempt to control neurogenic inflammation with the secretion of peptides such as somatostatin and β -endorphin.²⁸⁰ The primary effector cells in innate responses include natural killer cells, neutrophils, monocytes, and macrophages. Immature dendritic cells and T cells contribute to immunosurveillance during the progression of caries. Macrophages eliminate both pathogens and senescent cells while contributing to tissue homeostasis by repairing and remodeling tissue after inflammation.¹⁷⁵

Cytokines are small, cell-signaling proteins secreted by innate immune cells that induce phagocyte extravasation during inflammation. Chemokines secreted by odontoblasts, fibroblasts, immature dendritic cells, and macrophages stimulate leukocyte recruitment by directing monocyte and neutrophil migration extravascularly to sites of infection.¹⁷⁵ Prompt intervention, through removal of caries and bacterial antigens before irreversible pulpitis commences, can resolve inflammation (Fig. 24.2).

Dentin Regeneration and Reparative Tissue Formation

Mammalian dentin can be subdivided into primary, secondary, and tertiary types. Primary dentin is regular, tubular, and develops before eruption. Secondary dentin is also regular and formed throughout life. Tertiary dentin is more or less irregular and forms locally in response to caries or cavity preparation.²²⁸ It is also referred to as irritation dentin. Secondary dentin formation is slower than that of primary dentin as odontoblast activity is presumably downregulated by autophagocytosis after eruption.⁹⁵ A mild external stimulus to the odontoblasts leads to upregulated activity and tertiary dentin formation.^{350,353} Unlike bone, which is able to adapt to physiological changes throughout life, dentin is neither remodeled nor replaced once lost.³¹⁹

TERTIARY DENTIN FORMATION

Once dentin is exposed by caries, trauma, or cavity preparation, the tubules are opened and odontoblasts injured or even destroyed. If these challenges are of moderate intensity, they lead to a brief inflammation, which subsides when the irritant is removed. Thereafter, tertiary dentin is formed in the affected region.^{319,353} Minor trauma to the pulp stimulates undamaged primary odontoblasts to form new dentin.^{236,353,354} This tertiary dentin is therefore also referred to as a reactionary dentin, defined as dentin whose matrix is secreted by primary postmitotic odontoblasts in response to an adequate stimulus.^{236,353,354}

Injury to the dentin and odontoblast processes leads to a release of growth factors, which in turn leads to the upregulation of odontoblast activity.^{350,353} The probable control mechanism includes a series of tissue factors or signaling molecules, mainly from the TGF- β family released from the dentin matrix following injury.^{156,157} These growth factors can also be secreted by odontoblasts, promoted by acidogenic bacteria, or removed from the dentin by different rinsing solutions used during treatment such as ethylenediaminetetraacetic acid (EDTA), sodium hypochlorite (NaOCl), or citric acid.^{352,353} In addition, the application of calcium hydroxide (CH) or silicate cements (e.g., MTA or Biodentine) to dentin or

^aAdapted from Hahn and Liewehr.¹⁷⁵⁻¹⁷⁷




Fig. 24.2 A 15-year-old female patient presented with full orthodontic banding and deep cervical caries of the mandibular right first molar (tooth #30). The tooth was sensitive to cold and biting pressure. **A**, Periapical radiograph revealing large carious lesion and normal periapical structures. **B**, Clinical photograph showing advanced cervical caries extending below crestal gingiva. **C**, View of initial pulp exposure during caries excavation guided by caries detector dye. **D**, Photograph after complete caries removal, large pulp exposure and 6% sodium hypochlorite hemostasis. **E**, Clinical photograph after placement of thick white mineral trioxide aggregate aliquot over entire pulp and surrounding dentin. **F**, Radiograph showing pulp capped molar with temporary restoration (Photocore). **G**, Four-year radiographic control showing recurrent caries and fractured distal marginal ridge tooth #30. **H**, Five-year radiographic review showing no detectable apical pathosis and recently cemented full coverage porcelain fused to metal crown. The molar was asymptomatic and responded normally to sensibility testing. (© Dr. George Bogen 2019.)

onto pulp tissue leads to TGF- β 1 release.^{164,232,374} Residual dentin thickness has a significant influence on dentin formation. Even if the dentin above the pulp remains intact, not all odontoblasts will survive. In cavities with a residual dentin thickness of less than 0.25 mm, approximately 50% of cells

survive; in shallower cavities, this figure is 85% or more.²⁸¹ Despite odontoblast death, hard tissue formation can be observed. The reactionary dentin formation by the primary, postmitotic odontoblasts under these conditions is therefore a specific form of tertiary dentin.

MINERALIZED TISSUE FORMATION AFTER LOSS OF THE PRIMARY ODONTOBLASTS

The formation of mineralized tissue after loss of the odontoblasts is more complex than that of reactionary dentin. Dentin formation is not possible without odontoblasts. Nevertheless, after direct capping of a healthy, noninflamed pulp, hard tissue formation occurs. This mineralized tissue is heterogeneous, amorphous, and atubular. Therefore it differs histologically from primary and secondary dentin, but also from reactionary dentin. It is questionable whether this tissue can be called a “dentin bridge,” as it is not dentin from a histological viewpoint. If it really was further formation of dentin, a new type of cell would have to replace the destroyed primary odontoblast. The origin and differentiation of these initial cells remains unclear.³¹⁹

Recent investigations have found no histological evidence for the formation of replacement odontoblasts or new odontoblast-like cells after direct pulp capping (DPC) of human teeth with either CH or MTA.^{111,319,320} Secondary odontoblasts or odontoblast-like cells are therefore histologically not detectable in human teeth. It is uncertain whether the hard tissue formation is really dentin or just a dystrophic intrapulpal mineralization in response to inflammation.^{111,320} However, it is important to emphasize that both reactionary dentin (formed by primary odontoblasts) and hard mineralized repair tissue can form simultaneously in the same lesion.^{319,353}

Indications for Vital Pulp Therapy

The penetration of microorganisms and their metabolic products through dentin leads to an inflammation in the pulp. Mediated via cell receptors on odontoblasts, dendritic cells, and pulp fibroblasts, an immune response is initiated. This leads to hyperemia; the reaction is characterized by a decrease in cell number, a flattening of the odontoblasts, and the immigration of lymphocytes and plasma cells.³²¹ Clinically, this correlates with the development of reversible pulpitis, where healing could be facilitated by therapeutic intervention. If the stimulus persists, bacterial colonization in the pulp chamber can be detected, microabscesses and tissue necrosis lined with polymorphonuclear neutrophilic granulocytes become present, and inflammatory infiltrates are found in the periphery.³²¹ This is considered to be irreversible pulpitis.

Signs of a reversible pulpitis are a positive response to cold sensibility testing with radiating pain. An irreversible pulpitis is diagnosed on the (enhanced) positive sensibility test, on radiating irritant-persistent pain or lingering pain, pain on heat, and possibly on the patient's inability to localize the problem tooth. However, irreversible pulpitis may be asymptomatic.¹⁴ The correct diagnosis of pulp condition before DPC plays an important role in the outcome. Therefore, assessing the possible degree of inflammation and/or infection is required.²¹¹ It is challenging to assess pulp health accurately via clinical tests and to distinguish between altered and healthy pulps.¹¹

A positive sensibility test (cold) can give a variety of different diagnoses, depending on the severity and duration of response, guiding clinicians to different diagnoses. Teeth

responding to cold test may lead to a preoperative diagnosis of normal pulp, reversible pulpitis, or irreversible pulpitis dependent on subjective responses.³⁰¹ Sensibility testing does not precisely mirror the condition of the pulp, with 10% to 16% of results being false.¹⁹ Besides pain history and sensibility testing, hemorrhage after pulp exposure should be assessed. This may be a more reliable way to determine the status of pulpal infection than clinical signs and symptoms or sensibility testing.²⁵² Bleeding may reflect the level of inflammation of the pulp, with excessive hemorrhage usually indicating a pulp with a decreased or no chance of recovery.⁸⁸ The inflammatory response extends deeper into the pulp tissue when carious dentin is present during exposure, with possible bacterial penetration, compared to superficial inflammation when the pulp is just mechanically exposed.²²⁹

Pulps with profuse and lingering hemorrhaging had a significantly poorer outcome than those with modest bleeding or bleeding of short duration.²⁵² Clinically, bleeding should be controlled within 5 to 10 minutes.²¹¹ According to current recommendations in cases of irreversible pulpitis, the healing of the pulp tissue cannot be achieved predictably after removal of the triggering stimulus (e.g., caries). The diagnosis “irreversible pulpitis” often leads to the initiation of pulpectomy and root canal treatment. Although there is evidence that the histological observations described earlier correlate well with the clinical diagnosis, it should be noted that the clinical pattern of the complaint does not indicate the tissue's ability to regenerate.³²¹ In a paradigm shift, current clinical investigations using CSCs for full pulpotomies in adult teeth diagnosed with irreversible pulpitis and demonstrating radiographic periapical rarefaction have been treated successfully without pulpectomy and conventional orthograde treatments.^{22,23,25,211,242,363,364,386} Refer to the section Pulpotomy With Calcium Silicate Cements.

Maintaining pulp vitality can only be successful if bacterial infection of the tissue during and after the therapy is eliminated. Vital pulp treatments should generally be performed on teeth that do not show pronounced and unprovoked pain symptoms or severe pain on percussion. Vital pulp therapy should not be performed without a response to the sensibility test (in which the pulp status must be verified after pulp exposure) alongside radiographic evidence of periapical disease. In cases diagnosed with irreversible pulpitis, advanced treatment options such as CSC pulpotomy should be considered, especially in younger patients. All vital pulp treatment procedures require a quality bacteria-tight coronal restoration to preclude infection, with dental dam placement, the use of sterile instruments and complete excavation of caries. If not, root canal treatment should be given preference or extraction for teeth deemed unrestorable.¹⁰⁷

Favorable conditions exist in young patients with pulps without previous damage.³³⁴ With increasing age, a reduced ability for repair is expected due to pulpal changes characterized by a cell-poorer and more fibrous pulp tissue.^{161,285} Nevertheless, the age of the patient seems to play only a minor role in treatment success.^{23,101–103,206,211,242,243,248,258,363} The same applies to factors such as the sex of the patient, tooth position (posterior or anterior), and the size or location of the pulp exposure.^{110,206,244,260,301} The success rates of vital pulp therapies in the literature vary widely, especially in

the case of DPC after caries excavation. Early clinical failures (within days or weeks) are multifactorial, but certainly correlate with improper pulpal diagnosis or inability to identify and remove necrotic pulp tissue. An inaccurate pulpal diagnosis can underestimate the inflammatory status of the pulp, leading to irreversible pulpitis and pulp necrosis with postoperative pain.

The introduction of new bioactive materials, along with modified protocols, make more teeth with deep caries, traumatic injuries, and mechanical exposures viable candidates for innovative pulp therapies designed to maintain pulp survival. Outcomes depend on case selection, hemostatic agents, choice of pulp capping material, and the integrity of the sealed permanent restoration. The purpose in vital pulp therapy is to avoid or delay root canal treatment and advanced restorative care because these procedures, together, reduce long-term tooth survival compared to teeth with vital pulps.^{76,77,118,270,289,328,366,380,385}

Procedures Generating Mineralized Tissue Barriers

INDIRECT PULP CAPPING

Indirect pulp capping is defined by the American Association for Pediatric Dentistry (AAPD) as “a procedure performed in a tooth with a deep carious lesion approximating the pulp but without signs or symptoms of pulp degeneration. Indirect pulp treatment is indicated in a permanent tooth diagnosed with a normal pulp with no signs or symptoms of pulpitis or with a diagnosis of reversible pulpitis.”¹³ Hence indirect pulp capping is the permanent capping of a thin, pulp-nigh, cariously altered dentin layer, without complete excavation of the caries.³³ This may differ from the definition in other countries, for example, in the German-language literature, “indirect pulp capping” is defined as the treatment of a thin layer of caries-free dentin remaining above the pulp chamber with a medication.³³² The French definition of indirect pulp capping implies the covering of both healthy or carious dentin.²³⁰ These definitions may lead to confusion when interpreting the literature.

Clinically, this situation usually arises in the excavation of an extensive carious lesion, so that indirect capping is also called *treatment of deep carious lesions*. A more general term would be “treatment of the pulp-nigh dentin,” since indirect pulp capping may be necessary even in caries-free teeth, for example, after dental trauma.³⁵⁷ Because only a minimal dentin layer remains above the pulp tissue, there is a risk of irreversible inflammation of the pulp via the dentinal tubules.²⁸⁴ This can result from remaining bacteria or microorganisms actively entering the tissue and by cytotoxic components from restorative materials diffusing across thin residual dentin. Pulp-nigh dentin should be disinfected and bacteria-sealed with a capping material, stimulating the formation of tertiary dentin.³¹⁹ The indirect capping thus serves to protect the vital pulp, especially after caries removal. If there is already reversible pulpitis, a favorable environment for pulpal healing should be generated by indirect pulp capping (Fig. 24.3).

Advancing microorganisms and their by-products during the carious process pose a threat to the pulp.³²²

Therefore, during caries excavation, the number of microorganisms in the cavity and near the pulp should be reduced, with indirect capping completed under dental dam isolation. To prevent spread of microorganisms, it is recommended to disinfect the clinical crown with NaOCl (1% to 5%) or chlorhexidine digluconate (CHX, 2%) prior to excavation. After caries excavation, the cavity should be cleaned with NaOCl or CHX and water spray.^{53,75} Damage to vital tissue when using NaOCl is not of concern.³¹ Nevertheless, it remains unclear how much altered dentin can be left while allowing the pulp to heal.^{50,338} Hence indirect capping materials should eliminate potential residual microorganisms, neutralize any acidic (due to the carious defect) tissues, remineralize dentin, and stimulate the pulp to form tertiary dentin. Due to the disadvantages of aqueous CH suspensions, the use of CSCs can be seen as an improved alternative for indirect capping.⁹

DIRECT PULP CAPPING

Direct pulp capping is defined as “placing a dental material directly on a mechanical or traumatic vital pulp exposure” and “sealing the pulpal wound to facilitate the formation of reparative dentin and maintenance of a vital pulp.”¹⁴ The procedure is indicated for pulp exposures incurred as a result of caries removal, trauma, or tooth preparation. When mechanical exposures occur during tooth preparation, the exposed tissue is generally not inflamed. However, in cases of trauma or carious exposure, the degree of inflammation is the key predetermining prognostic factor. According to the American Association of Endodontists (AAE), “In a carious pulp exposure, underlying pulp is inflamed to a varying or unknown extent.”¹⁴ The major challenge in DPC is the proper identification and removal of the acutely inflamed or necrotic tissue compromised by long-standing proximity to oral microorganisms.²⁴⁷ Direct capping is therefore geared towards the healing of the pulp and the preservation of the tooth. If the pulp survives this treatment (remains vital), this can be considered a clinical success. Direct capping is a noninvasive, relatively simple and inexpensive treatment technique that, unlike root canal treatment, often does not require extensive restorative care.¹⁹⁸

Since Hermann's first publications in the late 1920s, CH has been used as an aqueous suspension for direct capping.¹⁸⁹ However, the published success outcomes of DPC in a carious field show significant variation and the procedure remains controversial. Some recent publications therefore recommend selective excavation and leaving carious tissue in the tooth, suggesting improved performance over direct capping. For a direct comparison of the two treatments, there are currently only three clinical studies available, two comparing 1- and 5-year data and the third showing 1-year data.^{25,51,52} In the second study, the prognosis of the two-stage excavation was compared with complete caries excavation treated by DPC or partial pulpotomy.⁵¹ Five years after two-step caries excavation, the pulp was vital in 60% of the cases, whereas in the same period the success rates after direct capping were only 6% and after partial pulpotomy 11%.⁵¹ The reason for lower success rates may include the absence of disinfection after pulp




Fig. 24.3 A 24-year-old male patient presented with a deep distal carious lesion extending to the inner pulpal quarter in a maxillary right second premolar. The tooth was symptomatic but responded normally to sensibility testing. **A**, Magnified bitewing radiograph showing extension of advanced caries close to coronal pulp. **B**, Preoperative radiograph with period indentical device for precise comparison. **C**, Eighteen-month radiographic review after indirect pulp capping completed with calcium hydroxide. **D**, Five-year radiographic control. Pulp sensibility test response was positive with a well-defined lamina dura demonstrated on the periapical radiograph. (Reprinted with permission, © Lars Björndal 2019.)

exposures, the choice of Dycal (Dentsply, Konstanz, Germany) as capping material, and the use of long-term provisional restorations.¹⁸¹ However, in the third study, where no pulp exposures were detected after complete caries removal, indirect pulp capping resulted in a 100% success rate at 12 months. The results indicate that CSCs may be preferable in indirect pulp capping procedures and that hard setting CH cements do not provide long- or short-term pulpal protection.¹⁸¹

PARTIAL PULPOTOMY

Partial pulpotomy (shallow or Cvek pulpotomy) is defined as the removal of a small portion of the vital coronal pulp as a means of preserving the remaining coronal and radicular pulp tissues.¹⁴ During clinical treatment, the decision to remove a small or large portion of the coronal pulp

is based on visual inspection of the tissue after pulp exposure during either caries excavation or exposure as a result of trauma (partial or shallow pulpotomy).¹⁴⁵ The incorporation of the dental operating microscope (DOM) is highly recommended. The coronal pulp is reduced from the exposed site by approximately 2 to 3 mm in order to remove necrotic or potentially inflamed and irreversibly damaged tissue, keeping the remaining pulp vital.⁴⁹ Partial pulpotomy is preferably performed with a high-speed handpiece and a small round diamond bur with copious water spray or continuous rinsing with physiological saline solution.^{135,140,165}

After partial tissue removal, if bleeding cannot be controlled after 5 to 10 minutes of direct exposure to NaOCl, complete removal of the coronal pulp to the pulp floor is the preferred option.²¹¹ NaOCl is a valuable diagnostic as well as clinical tool to differentiate irreversible from reversible

pulpitis in the coronal pulp in order to help determine whether to proceed with partial pulpotomy, complete pulpotomy, or pulpectomy. This decision can be of paramount importance in young permanent teeth with open apices, in which removal of tissue contaminated by microorganisms can reverse symptoms and stabilize inflamed tissue.^{89,130,390}

A recent study that examined MTA complete pulpotomies suggested that a hemorrhage “control time” parameter is not an accurate indicator of pulpal inflammatory conditions, contrary to other investigations.²⁴² However, the

study did not benefit from recommended protocols including verified necrotic tissue removal using the DOM. Investigations have shown that the inflammatory response of pulp tissue challenged by bacterial by-products can progress several millimeters into the coronal pulp or advance further, thus affecting the radicular pulp tissue distant from the injury site.³²⁰ The removal of 2 to 3 mm of exposed coronal tissue or radicular tissue to access the deeper, healthy tissue, in cases of trauma, carious exposures or complete pulpotomies can ensure pulp survival (Fig. 24.4).¹⁰¹



Fig. 24.4 An 7-year-old male patient referred after trauma displaying a horizontal coronal fracture of his maxillary right central incisor #8 with a pulp exposure covered with a glass ionomer cements by the general dentist and a retained deciduous left central incisor (F). **A**, Clinical photograph showing horizontally fractured right maxillary incisor and retained deciduous left central incisor. **B**, Periapical radiograph reveals open apex #8 and unerupted maxillary left permanent incisor #9. In addition, a mesiodens is visible. **C**, Photograph after shallow Cvek coronal pulpotomy. **D**, View of access cavity after sodium hypochlorite hemostasis and placement of 3 to 4 mm Biodentine (Septodont, Saint-Maur-des-Fossés, France) plug. **E**, Radiograph after pulpotomy and temporary restoration placement. **F**, Clinical photograph 3 days after verified calcium silicate cements setting and reattachment of the fractured coronal segment after bonding. **G**, Radiograph of #8 with bonded crown segment reattachment showing immature open apex.




Fig. 24.4, cont'd **H**, Clinical photograph of full mouth banding after extraction of (F) and the mesiodens to permit normal eruption of tooth #9. **I**, Four-year clinical photograph with full orthodontic banding and complete eruption of #9 into the occlusal plane. Tooth #8 responded normally to cold sensibility testing at 1-, 2-, and 3-year recalls. **J**, Four-year periapical radiograph showing root-end closure of tooth #8 with normal periapical appearance. **K**, Five-year radiographic review of tooth #8 demonstrating complete radicular maturation. The incisor responded positive to cold testing. **L**, Clinical photograph at 5 years after finishing of a resin composite veneer created with a layering technique on tooth #8. (Courtesy Dr. Marga H. Ree with restoration by Dr. Caroline Werkhoven, Amsterdam, Netherlands.)

The amputation site is covered with a NaOCl soaked cotton pellet until hemorrhage ceases. If the formation of a blood coagulum is prevented, the same pulpal repair mechanisms associated with DPC are expected.^{102,191} If the remaining pulp is healthy, bleeding can be stopped within 5 to 10 minutes. If hemostasis does not succeed within this time, it indicates that the pulp is irreversibly inflamed, and a complete pulpotomy (the removal of the entire coronal pulp) may be considered as a last resort to maintain vitality.²²⁵ A CH suspension or CSC is applied to the newly exposed pulp surface and covered with a cement (for the CH suspension) or a thin layer of flowable composite, compomer, or RMGI (for the CSC).⁹² A current study examining MTA versus CH pulpotomy has shown superior performance by MTA in mature permanent teeth compared with a hard-setting CH (Dycal). Since the capping material is used in larger quantities in the partial pulpotomy than in the DPC, the risk of tooth staining is considered higher when using a bismuth oxide containing CSC.²²⁵ Partial pulpotomy and DPC are similar procedures, differing only in the amount of vital pulp tissue remaining after treatment. Partial pulpotomy is the preferred option in elective treatment procedures for teeth diagnosed with anatomic anomalies, such as dens evaginatus and invaginatus.

COMPLETE PULPOTOMY

Complete pulpotomy, or *complete pulp amputation*, is a more intrusive procedure defined by the AAE as “the removal of the coronal portion of the vital pulp as a means of preserving the vitality of the remaining radicular portion: may be performed as emergency procedure for temporary relief of symptoms or therapeutic measure, as in the instance of a Cvek pulpotomy.”¹⁴ The entire coronal pulp is removed and the vital pulp tissue capped at the entrance level of the root canal orifice. After successful hemostasis, it is treated analogously to DPC (Fig. 24.5).²²⁵

The assessment, selection, and amount of tissue removal are dependent on observer experience and completed on a case-by-case basis using magnification. Generally, after necrotic coronal tissue is completely removed, the inflamed pulp can be partially or completely amputated to the pulp floor or cervical area (pulpotomy) in the case of molars and some premolars.^{144,147} The remaining tissue requires hemostasis before the placement of a CSC. The AAPD guidelines state, “A pulpotomy is performed in a tooth with extensive caries but without evidence of radicular pathology when caries removal results in a carious or mechanical pulp exposure.”¹³ However, the guideline requiring an absence of apical pathosis before pulp exposure for pulpotomy procedures may be outdated and require modification. Growing evidence from contemporary




Fig. 24.5 A 10-year-old female was referred with a mandibular right first molar pulp exposure generated during caries excavation and temporized by the general dentist. **A**, Radiograph showing open apices with no evident apical pathosis. The tooth was diagnosed with reversible pulpitis. The patient received a new resin composite buildup to provide better isolation before a complete pulpotomy was performed. **B**, Clinical photograph of access opening through the buildup showing a sterile cotton pellet on the pulpal floor saturated with 5% sodium hypochlorite (NaOCl) for hemostasis. **C**, Photograph of radicular pulp in orifices after complete pulpotomy and 5% NaOCl hemostasis. **D**, View through access opening after 5 mm thickness white mineral trioxide aggregate (MTA) (ProRoot MTA, Tulsa/Dentsply, Tulsa, OK) placement onto radicular pulp tissue and pulpal floor. **E**, Postoperative radiograph showing white MTA with wet cotton pellet and provisional restoration. One month later, MTA setting was verified and a permanent composite restoration provided. **F**, Radiographic review at 6 years shows apical maturation and thickening of the root walls. The patient remained asymptomatic and the tooth responded positively to electric pulp testing. (Reprinted courtesy Dr. Marga H. Ree, Purmerend, Netherlands, with permission.)

studies shows resolution of radicular lesions after pulpotomy treatments using CSCs in adult teeth diagnosed with irreversible pulpitis.^{20,22,23,25,242,361–363}

Complete pulpotomy has traditionally been recommended for primary and immature permanent teeth for which short-term outcomes are generally favorable. However, the treatment of mature permanent teeth can be traced to Roman times around 200 BC.⁴¹⁵ Since the introduction of CSCs, there has been a renewed interest in pulpotomy as an alternative option to conventional orthograde root canal treatment, particularly in mature adult

permanent teeth. Ongoing clinical investigations strongly support the use of CSCs for pulpotomy procedures in these teeth and show acceptable outcomes in pain reduction with continued normal function.^{21–23,25,211,242,363,364,386}

Materials for Vital Pulp Therapy

For successful pulp capping outcomes, the removal of noxious stimuli, control of any infection, and the biocompatibility of the capping material are important prerequisites.^{55,75} It has

been shown that rat pulp, in the absence of microorganisms, has the regenerative power to seal an exposed pulp with mineralized tissue even without medication or the use of restorative materials.^{210,306} The presence or absence of microorganisms is the determining factor in the healing of pulp tissue.²¹⁰ The tissue reactions that follow capping (for instance, collagen synthesis and secretion) are generally similar to connective tissue injuries.^{334,353} While excavating a deep caries lesion or during trauma, dentin or pulp tissue areas can be directly exposed, which are particularly permeable due to the structure of dentin. Closer to the pulp chamber, dentinal tubules occur more frequently per square millimeter and have larger diameters than further from the pulp.³³⁶

Since microorganisms, bacterial toxins (lipopolysaccharides), and many restorative materials can damage the exposed pulp tissue or diffuse via the dentinal tubules, causing irritation, both the pulp and the surrounding dentin should therefore be covered with the indicated capping material. Alternatively, pulp capping materials must create an artificial barrier between the vital pulp and the oral cavity to prevent the ingress of microorganisms. Moreover, the capping material should have antimicrobial properties without being toxic to the pulp.¹⁰⁸ In addition to the disinfection and sealing of dentin, another requirement of the capping material is hard tissue regeneration by pulp cell induction and thus preservation of pulpal vitality.^{128,273,334} Mineralized tissue regeneration can occur in healthy pulps beneath a variety of capping materials.¹⁵ The healing of pulp wounds is therefore not associated with a special drug or wound dressing.⁴⁴ However, medications to treat an exposed pulp should promote the innate capacity of pulpal cells to form hard tissue.³³⁴

AQUEOUS CALCIUM HYDROXIDE SUSPENSIONS

CH has long been considered the universal standard material for vital pulp therapy. Although the material demonstrates many advantageous properties, long-term study outcomes in vital pulp therapy have been inconsistent.^{30,40,42,196} Desirable characteristics of CH include an initial high alkaline pH, which is responsible for stimulating fibroblasts and enzyme systems. It neutralizes the low pH of acids, shows antibacterial properties, and promotes pulp tissue defense mechanisms and repair. The drawbacks of CH include weak marginal adaptation to dentin, degradation and dissolution over time, and resorption in primary teeth. Histologically, CH demonstrates cytotoxicity in cell cultures and has been shown to induce pulp cell apoptosis.^{15,159,335}

Tunnel defects have also been demonstrated in hard tissue barriers generated over pulp wounds associated with both CH and CSCs.^{10,15,38,98,99,159,162,275,334} However, the primary difference between the two agents is that CH products are absorbable over time and dimensionally unstable. The slow disintegration of the CH after mineralized tissue formation can allow microleakage, permitting a slow ingress of microorganisms through defects. This can induce subsequent pulpal degeneration and lead to potential dystrophic calcification and pulp necrosis. Over extended periods, this problematic outcome can complicate any necessary nonsurgical root canal treatment at a later date.²⁷⁴

Clinical retrospective investigations have shown variable success rates over 2- to 10-year recall periods for direct CH

pulp capping in humans.^{30,40,42,196} Two current studies have examined the efficacy of CH as a DPC agent. One examined the survival of 248 pulp-capped teeth that were diagnosed either as having normal pulps or exhibiting spontaneous pain; the researchers found an overall survival rate of 76.3% with an average recall period of 6.1 years.¹¹⁰ Outcomes were less favorable for teeth showing spontaneous pain, in older compared to younger patients, and in teeth restored with glass ionomer cements (GIC). The probability of pulps becoming nonvital after CH pulp capping was greater within the first 5 years of treatment.

The second study observed 1075 teeth directly pulp capped with a CH-based agent; these teeth had either healthy pulps or showed signs of reversible pulpitis.²⁸⁸ Inclusion criteria limited pulp chamber roof exposures to no larger than 2 mm in diameter. Successful outcomes were 80.1% after 1 year and 68% after 5 years; this diminished to 58.7% after a 9-year observation period.³⁹⁵ The results demonstrate increasing failure rates over time, attributable to absorption of the material under permanent restorations proximal to hard tissue bridges with tunnel defects. Another investigation has confirmed decreasing success rates with CH pulp capping with extended recall periods.²⁵⁸ CH clearly has many favorable characteristics, but it can no longer be considered the preferred agent in vital pulp therapy (Fig. 24.6).^{134,193,258,260,286}

HARD SETTING CALCIUM HYDROXIDE CEMENTS

In contrast to aqueous CH suspensions, other CH combinations such as cements (calcium salicylate ester cements) as well as liners or putties are less suitable for pulp capping due to a lower release of hydroxyl ions. In these preparations, the resulting pH is lower and the antimicrobial effect is significantly weaker.¹³⁹ In addition, hardening calcium salicylate ester cements (e.g., Dycal; Life, KerrHawe, Bioggio, Switzerland) are characterized by long-term disintegration.³⁸ They also fail to provide permanent support for the final restoration.⁹⁹ New mineralized tissue formation below CH-salicylate ester cements can be slow to generate and be less uniform in shape. Hard tissue regeneration may therefore be weaker using these CH preparations. In addition, inflammation is more common than with CH suspensions.³³⁴ Some additives that harden the CH preparations may even have a toxic effect on the pulp.^{99,334} For direct capping or pulpotomy, hard setting CH cements based on calcium salicylate esters cannot be recommended.

LIGHT-CURING LINERS AND CEMENTS

To compensate for the disadvantages of proven CH preparations, light-curing liners and cements with CH additives were developed (e.g., Ultrablend Plus, Ultradent, South Jordan; Calcimol LC, VOCO, Cuxhaven, Germany). These materials do not have sufficient mechanical strength despite their composite content, and specific CH effects are minimal.³⁵⁹ Moreover, the pH of these products is significantly lower compared to other CH products.³⁵⁹ Nonetheless, antibacterial effects can be detected in vitro, although this has not been confirmed by other studies.^{309,402} The cytotoxicity of these products, which is due to the composite component, has been clearly demonstrated.^{184,309,310} Therefore according to the




Fig. 24.6 Reparative bridge formation compared in dog pulps using mineral trioxide aggregate (MTA) and calcium hydroxide (CH). **A**, Two-week pulp response to CH showing inflammatory cells (IC). **B**, Tissue specimen showing lack of bridge formation and disorganized tissue proximal to CH. **C**, An 8-week specimen with partial reparative bridge (RB) formation subjacent to CH. **D**, Two-week pulpal response to MTA showing notable barrier formation and layer of organized odontoblast-like cells (OLC). **E**, Pulp tissue section demonstrating complete calcific bridge formation proximal to MTA at 4 weeks. **F**, Sample section pulp capped with MTA at 8 weeks showing organized hard tissue formation with no inflammatory cell infiltrate. (Loma Linda University, Loma Linda, CA.)

manufacturer's instructions, the direct contact of Calcimol LC to pulp cells should be avoided.

Another light-curing product is TheraCal LC (Bisco, Schaumburg, IL). The spectrum of indications according to the manufacturer corresponds to that of MTA and other CSCs. Unlike all other CSC products, where a cement powder must be mixed with a liquid (water), TheraCal LC consists of 45% Portland cement CEM III and 45% composite resin and is therefore photopolymerizable, significantly simplifying its clinical use.^{154,155} However, it is known that all the monomers in TheraCal LC are cytotoxic in vitro.^{180,202,207} After 1 day of direct contact with TheraCal LC, the fibroblast cell turnover rate decreased by 31.5% and after 1 week to 45.9%.¹⁸⁴ After 72 hours of contact with TheraCal LC there was a marked decrease in the percentage survival of the cells.³¹⁰ For tissue healing (hard tissue formation after pulp capping), it is crucial that there is no decrease but an increase in the cell turnover rate. In contrast to TheraCal LC, other calcium silicate products and CH have been shown to induce pulpal cell proliferation.^{112,113}

Similar to other light-curing liners using CH, TheraCal LC exhibits a significant cell-damaging effect when in direct contact with human dental pulp stem cells.^{58,184,309,310} It is also unclear how much Portland cement can be released from the resin matrix when the material is polymerized. After curing, TheraCal LC shows a heterogeneous structure with a high proportion of large, unhydrogenated particles, since the resin additives do not provide enough moisture to allow hydration. The hydration of TheraCal LC (the reaction of cement with water) is incomplete because of limited moisture diffusion within the material. Thus, no CH and only a small amount of calcium ions are released.⁷⁰ Light-curing liners and cements with added CH or MTA are collectively cytotoxic.^{309,310} It is currently inadvisable to use

photopolymerizable CH or calcium silicate-containing materials for indirect or DPC.

COMPOSITE RESINS, DENTIN ADHESIVES, AND RESIN-MODIFIED GLASS IONOMER CEMENTS

Adhesive systems were introduced in the early 1980s as potential agents for DPC of cariously and mechanically exposed pulps.^{200,253,404} Dentin adhesives, hydrophilic resins, and RMGI cements initially showed favorable outcomes in preliminary pulp capping investigations with nonhuman primates, based on standards set by the International Organization for Standardization.^{96,367–369} However, the transitional use of these materials in human subjects did not demonstrate the corresponding biocompatibility or consistent reparative bridge formation.^{5,119,159,183,197,271} Investigations that have examined responses to resin-based materials in human teeth have demonstrated unfavorable histologic reactions when the material is placed directly or in close proximity to pulp tissue.^{5,124,172,272,315} Histological material typically demonstrates inflammatory cell infiltrates consistent with pulp cell cytotoxicity, subclinical adhesive failures at the pulp interface, and a profound absence of biocompatibility.^{5,119,272,296,315,349}

The application of dentin adhesive to a thin layer of dentin (0.5 mm) leads to an expansion of the blood vessels and chronic inflammation of the pulp tissue.¹⁸³ Nonpolymerized or partially polymerized dentin adhesives cause apoptosis in various pulp cells, such as macrophages and undifferentiated pulp cells.²⁴⁶ Besides monomers from dentin adhesives, identical cytotoxic components can also be released from composites, which then penetrate through dentinal tubules to pulp tissue causing damage.⁵⁹ Also, deep cavities (without pulp exposure) are problematic because the residual dentin thickness over the pulp can be thin, and tubular fluid can

prevent complete polymerization. In addition, complete polymerization can be prevented by an excessively thick composite layer that is insufficiently penetrated by curing lights.²⁷² Both factors lead to an increased proportion of residual-free monomers, which are then released from the composite resin and diffuse into the pulp tissue. In clinical studies the use of dentin adhesives in deep cavities results in relatively frequent pulp necrosis.³³⁷

Unpolymerized, polymerized, and aged dentin adhesives release cytotoxic components that are responsible for inferior performance in human and animal experiments.^{5,94,112} In addition, monomers from restorative materials (dentin adhesives/composites) may interact with the immune system of the pulp, weakening its defense against invading microorganisms.^{44,268} Direct contact with dentin adhesives or composite resins is thought to reduce pulpal defense, either due to cytotoxicity or specific changes in the immune response.^{207,267,268} Adhesive components thus inhibit the proliferation of immunocompetent cells and cause chemical immunosuppression, which promotes the development of pathological changes in the pulp.^{44,207} Dentin adhesives and composites are essentially not biocompatible and should not be used for indirect or DPC.^{9,94} However, hydrophilic resins and RMGI cements provide excellent seals when they are combined with light-cured composites as permanent restorations and placed directly over pulp capping materials such as MTA and other CSCs.^{27,131,288}

MINERAL TRIOXIDE AGGREGATE

MTA was introduced as a pulp capping agent by Torabinejad and associates in the mid-1990s.¹⁴¹ Most preliminary experimental and current clinical data in vital pulp therapy are based on the proprietary material ProRoot MTA (Tulsa/Dentsply, Tulsa, OK). The cement consists of a hydraulic calcium silicate powder containing oxide compounds, including calcium oxide, ferric oxide, silicon oxide, sodium and potassium oxides, magnesium oxide, and aluminum oxide.⁷¹ The material exhibits favorable physicochemical characteristics that stimulate reparative dentinogenesis by recruitment and activation of hard tissue-forming cells, contributing to matrix formation and mineralization.²⁹⁸ Soluble cytokines and growth factors that mediate wound repair of the dentin-pulp complex are nested in the extracellular matrix. MTA stimulates reparative hard tissue formation by sequestering these growth factors and cytokines embedded in the surrounding dentin.^{222,223,375,385}

CH and calcium silicate hydrate, the principal by-products formed during hydration of mixed MTA, contribute to a sustained alkaline pH.^{68,143} The setting properties of the hydroscopic silicate cements are not affected by the presence of tissue fluids or blood.³⁷⁷ They are therefore also referred to as “hydraulic” cements, as they are hard setting both in contact with air and water.⁴⁷ During the setting process, the gradual release of calcium ions encourages reparative barrier formation by promoting signaling molecules, such as VEGF, macrophage colony-stimulating factor, TGF- β , and interleukins IL- β and IL-1 α .^{251,300}

MTA demonstrates superior marginal adaptation to dentin compared to CH-based agents and forms a dense bond to dentin. Mineral components from the cement penetrate

into the tubules, producing adhesion to dentin comparable to GICs.^{29,216} MTA also forms an adherent interfacial layer during mineral nucleation at the dentin surface that appears similar in composition to hydroxyapatite when examined with x-ray diffraction, energy-dispersive x-ray analysis, and scanning electron microscopy (SEM).^{298,329,379} Similar to CH, MTA induces an inflammatory cascade that results from calcium ion release and the creation of an alkaline environment, producing tissue necrosis. Both MTA and CH have been shown to stimulate and increase the Höhl cell mitosis index in rodents.^{114,115}

MTA activates the migration of progenitor cells (fibroblasts) from the central pulp to the injury site and promotes their proliferation and differentiation into odontoblast-like cells without inducing pulp cell apoptosis.²⁹⁸ MTA also stimulates *in vitro* the production of messenger RNA and increases protein expression of the mineralized matrix genes and cellular markers crucial for mineralization after matrix formation.²⁹⁸ In a human study, odontoblast-like cells and the formation of a dentin or dentin-like tissue could not be proven after DPC with MTA (RetroMTA; BioMTA, Daejeon, Korea). Hence the new calcified hard tissue was not “regular dentin” and did not seem to be the product of genuine odontoblast differentiation. This observation is identical to results after DPC with CH. Hard tissue formation after DPC appears to be a dystrophic intrapulpal mineralization in response to the capping procedure.¹¹¹

Gray MTA has been shown to enhance cell proliferation and survival of cultured human dental pulp stromal cells.³⁰⁰ The biocompatibility of set MTA upregulates the expression of transcription factors, angiogenic factors, and gene products, such as dentin sialoprotein, osteocalcin, and alkaline phosphatase.²⁹⁹ Odontoblast signaling proteins are essential in the differentiation of progenitor cells into cells responsible for repair and hard tissue deposition.^{299,300} After MTA pulp capping, both sialoprotein and osteopontin have been observed in the mineralized hard tissue matrix at the exposure site during the process of reparative hard tissue formation.²²⁷

Dental pulp cells differentiate into the odontoblastic cell line in the presence of the signaling molecules, such as TGF- β , heme oxygenase-1 enzyme, and bone morphogenetic proteins BMP-2, BMP-4, and BMP-7.¹⁷¹ MTA most likely upregulates fibroblast secretion of BMP-2 and TGF- β 1 and therefore stimulates and promotes mineralization and hard tissue regeneration.^{117,170,171,178,340,365,406} MTA induces a time-dependent environment that is pro-inflammatory and promotes wound regeneration through upregulation of cytokines.³¹⁸ Immunohistochemical analyses show that cytokines, including myeloperoxidase, inducible nitric oxide synthase, VEGF, nuclear factor-kappa B, activating protein-1, and cyclooxygenase-2, show increased expression in the presence of MTA. Cytokine upregulation is responsible for inducing biomineralization by producing apatite-like clusters on collagen fibrils at the MTA-dentin interface. MTA does not affect the generation of reactive oxygen species, thereby positively influencing cell survival. MTA also has been shown to improve the secretion of IL-1 β , IL-6, and IL-8.^{67,81,91} However, an inhibitory effect on dental pulp cells has been demonstrated in the presence of MTA, which may be attributed to the release of aluminum ions.²⁶⁷ Overall, the

data indicate that MTA promotes a biocompatible, noncytotoxic, antibacterial environment and surface morphology that is favorable for reparative calcific bridge formation. MTA stimulates the release of the dentin matrix components necessary for hard tissue repair and regeneration in mechanically exposed healthy and partially inflamed pulps (Figs. 24.7–24.9).^{6,141,170,266,286,317,374}

One disadvantage of MTA is that it can lead to discoloration of the hard tooth tissue. This may be problematic, particularly

in anterior teeth during trauma management.²⁷⁹ It is due to heavy metals contained in MTA, such as bismuth oxide used for radiopacity or iron.^{45,123,347} The discoloration is mainly induced by the oxidation of these metals after contact with NaOCl or the uptake of blood components.^{69,234,347} Other CSCs contain less or minute levels of heavy metals and their potential to discolor teeth is minimal. CSCs containing zirconium oxide or tantalum oxide, which are used as radiopacifiers, are particularly color-stable.²⁷⁹




Fig. 24.7 A 50-year-old male patient with deep recurrent caries associated with a mandibular right first molar (#30). The patient had no history of pain and responded normally to cold testing. **A**, Periapical radiograph showing distal caries in the mandibular right second premolar (#29) and large carious lesion below mesial aspect of composite restoration in the molar. Note retained deciduous root tip mesial to tooth #29 and normal periapical appearance of #30. **B**, Pulpal hemorrhaging evident after complete caries removal with hand excavators. **C** and **D**, Clinical photographs after bleeding was controlled using cotton pellets soaked in buffered 0.5% sodium hypochlorite (NaOCl). Note presence of reparative dentin protecting mesiolingual pulp horn (red arrow). A 2 mm-thick layer of white mineral trioxide aggregate (Dentsply, Tulsa Dental, Tulsa, OK) placed directly over the exposure and surrounding dentin and covered with a thin wet cotton pellet. The tooth was provisionalized for 1 week and restored permanently with composite resin. **E**, One-year radiographic follow-up; tooth responded normally to cold sensibility testing. **F**, Control radiograph at 3 years. Patient was asymptomatic and exhibited normal pulp testing response. (Courtesy Dr. Rita Kundzina, Tromsø, Norway.)



Fig. 24.8 Symptomatic mandibular left first molar in a 32-year-old male patient with temporary restoration placed over deep caries on the distal aspect and referred for root canal treatment. Sensibility testing elicited a normal pulpal response. **A**, Periapical film showing deep caries extending towards the distal pulp horn. **B**, Radiograph of direct mineral trioxide aggregate (Dentsply, Tulsa Dental, Tulsa, OK) pulp capping after 5.25% sodium hypochlorite hemostasis and placement of a three-surface bonded composite restoration. **C**, Nine-year 6-month radiographic control. The tooth was positive to cold testing and without symptoms. Note presence of mesial carious lesion in the second molar. (© Dr. George Bogen.)




Fig. 24.9 **A**, Periapical radiograph of deep caries in a partially symptomatic mandibular left first molar in a 29-year-old female patient. **B**, Direct pulp capping completed with white mineral trioxide aggregate (MTA); the final bonded restoration was placed during the second visit after MTA curing. **C**, Radiographic recall at 7 years. Tooth was asymptomatic with normal response to CO₂ ice. **D**, Thirteen-year 10-month recall radiograph showing normal periapical appearance. The molar responded positive to cold testing and demonstrated normal mobility and periodontal probings. (© Dr. George Bogen.)

CALCIUM SILICATE CEMENTS

A variety of new CSCs have developed since the introduction of MTA.^{116,153,232,302} Preliminary investigations have demonstrated physicochemical and bioinductive properties comparable to MTA, indicating promise for their application in vital pulp therapy.^{18,57,127} Some of these tricalcium-based materials include BioAggregate (Innovative Bioceramics, Vancouver, BC, Canada), Biodentine (Septodont, Saint-Maur-des-Fossés, France), MTA-Angelus (Angelus, Londrina PR, Brazil), MTA Bio, and MTA Branco (Angelus).^{160,237} Other formulations include EndocemMTA (Maruchi, Wonju-si, Gangwon-do, South Korea) and EndoSequence BC root repair material

(Brasseler USA, Savannah, GA). Currently, there are more than 40 different CSC formulations from international manufacturers. Some other silicate cement products include Endo-Binder, iRoot BP, MicroMega MTA, MTA Bio, MTA Plus, NeoMTA Plus, RetroMTA, Tech Biosealer Capping, TheraCal LC, CEM Cement (calcium-enriched mixture), Grey MTA Plus, MEDCEM MTA, EndoCem Zr, Channels MTA, DiaRoot Bioaggregate, and Harvard MTA.³⁰² Additional compounds are currently undergoing clinical investigations to establish their safety and efficacy.^{219,278,302,378}

The main components of MTA and the new CSCs are tricalcium silicate and dicalcium silicate, the major components of

Portland cement. Hydraulic tricalcium silicates promote reparative barrier formation by the upregulation of transcription factors after gaining immediate strength on hydration. The cements also encourage hydroxyapatite crystal formation on the cement surface when in contact with calcium- and phosphate-containing fluids.^{155,179} Moreover, the release of CH from CSCs during hydration has a positive effect on cell regeneration. Osteoblasts, cementoblasts, periodontal ligament cells, and pulp cells are deposited directly on the CSC surface, as the material is recognized as “non-foreign,” which affirms the high biocompatibility of these cements.³⁷⁸

In addition to CH, silicon is released during CSC cement hardening. The exact function of silicon in the metabolic processes of hard tissue formation is unclear, but it is believed to play a role in the early stages of mineralization.⁸⁰ It is also known that silicon positively influences the rate of new hard tissue deposition when it is released from bioactive materials such as MTA.³⁰⁴ In addition, silicon can remineralize demineralized dentin in vitro and this has also been demonstrated for CSCs.^{28,304,327} It can be concluded that the release of silicon from calcium silicate-containing materials contributes to the induction of mineralized tissue formation.¹⁷⁹

BioAggregate is a bioinductive tricalcium cement that can induce mineralization in osteoblast cells by increasing levels of osteocalcin, collagen type 1, and osteopontin gene expression.⁴¹² Hydration of the cement results in the formation of calcium silicate hydrate and CH, showing high concentrations of silica and calcium phosphate.¹⁶⁶ This characteristic is consistent with materials used in vital pulp therapy to promote hard tissue formation. Investigations using x-ray diffraction show the material to have a composition similar to that of MTA, but BioAggregate contains tantalum rather than bismuth oxide for radiopacity.³⁰³ It demonstrates remarkable biocompatibility compared to MTA, inducing cell differentiation in both human periodontal ligament and gingival fibroblasts.^{361,405} Both fresh and set mixtures of MTA and BioAggregate have shown antimicrobial properties effective against *Enterococcus faecalis* in vitro when combined with equal amounts of human dentin powder.⁴¹⁴ The material also shows a greater resistance to dislodgement in an acidic environment compared to MTA, and higher fracture resistance when used as a filling material.^{182,383}

Biodentine is a tricalcium silicate-based cement that also demonstrates exceptional bioactive properties.² Whereas MTA is more or less comparable to a refined Portland cement, Biodentine consists mainly of pure tricalcium silicate (about 80%) with calcium carbonate as filler (about 15%).^{47,109} Zirconium oxide is added as radiopacifier (about 5%). In contrast to other CSCs and MTA, Biodentine does not contain dicalcium silicate or metal oxides except the radiopacifier.^{72,341} The liquid consists of calcium chloride in an aqueous solution with an admixture of modified polycarboxylate. The powder is mixed in a triturator with the liquid in a capsule. Once mixed, Biodentine sets in about 15 minutes minimum, and hardens completely in 85 minutes.²¹⁷

Biodentine does not induce genotoxic or cytotoxic effects when measured with the Ames mutagenicity test. It is considered a biocompatible dentin replacement material for use under restorative materials as a base.²³² During setting,

Biodentine releases calcium ions forming CH that lead to an alkaline pH in the surrounding tissues, inhibiting the growth of microorganisms.^{48,70} Furthermore, when Biodentine is applied onto pulp cells ex vivo, TGF- β 1 is released.^{231,250} In vitro Biodentine induces proliferation, migration, and differentiation of human dental pulp cells and induces cell proliferation in osteoblasts and periodontal ligament cells.^{17,209,232,307}

These factors may explain hard tissue formation after DPC with Biodentine.² The material stimulates biomineralization and encourages hard tissue formation when used as a capping material.^{343,413} Histological evaluation in humans revealed complete mineralized tissue formation 6 weeks after DPC with mild to absent pulp inflammatory reactions, comparable to MTA.^{295,297} Biodentine forms needle-like crystals resembling apatite at the dentin interface.¹²⁰ Identically to MTA, Biodentine seals dentin by micromechanical retention with a shear bond strength comparable to GICs.^{29,216} Different light-curing adhesive lining materials are able to bond to Biodentine and may prevent bacterial leakage.^{2,333} After indirect capping with Biodentine, a reversible pulpitis can reproducibly heal.¹⁸² Success rates of human DPC with Biodentine are between 82.6% and 86% after 1.5 to 2.3 years and thus in the range given for ProRoot MTA (Figs. 24.10 and 24.11).^{181,193,206,226,244,248,260}

Another promising material for vital pulp therapy is MTA-Angelus, which has a basic formulation of 25% bismuth oxide and 75% Portland cement. The composition eliminates calcium sulfate, providing a short setting time of 15 minutes, preferable for pulp capping or pulpotomy procedures.⁵⁷ Variations in bismuth oxide and the presence of iron characterize the chemical composition of MTA-Angelus, and the crystalline structures formed on hydration are similar to gray and white ProRoot MTA.³⁵⁵ These materials have been compared experimentally as pulp capping agents in intact, caries-free human teeth. Histomorphologic examination of the extracted teeth revealed similar inflammation and hard tissue formation responses.⁴ MTA-Angelus also demonstrates antifungal properties and a lower compressive strength than ProRoot MTA.^{41,212,219} Many CSC materials demonstrate acceptable antibacterial products; however, *E. faecalis* has shown resistance to some cements when measured with disc diffusion tests.²¹⁹

EndoSequence BC root repair material shows low cytotoxicity, antibacterial activity against *Enterococcus faecalis*, and potential as a pulp capping material.^{105,416} Another material, calcium-enriched mixture (CEM) cement, has also demonstrated excellent physical and biologic properties in vital pulp therapy investigations.^{20–24,26,294} The advantages of these calcium silicate materials over the typically used CH products lie in the higher mechanical strength, lower solubility, and tighter sealing to dentine. Major disadvantages of CH are avoided when using CSCs: dissolution of the capping material as well as the mechanical instability and consequent lack of long-term protection against bacterial microleakage.¹⁰⁸ The new generation of CSCs appear promising when used as vital pulp therapeutic agents, and current investigations appear to support their future potential and expanded use in vital pulp therapy.




Fig. 24.10 **A**, Bitewing radiograph of quadrants 2 and 3 showing defective restoration in a mandibular left first molar (#19) of a 27-year-old female patient. **B**, Clinical photograph showing pulp exposure (white arrow) after cavity preparation and complete caries excavation. **C**, Pulp capping and restorative base completed under slight pressure using Biodentine (Septodont; St. Maur-des-Fossés, France). **D**, Clinical photograph of final two-surface composite restoration placed after a setting time of 15 minutes. The restoration was placed after acid etching and bonded with a two-bottle dentin adhesive system. **E**, One-year periapical radiograph showing a normal periapical region and Biodentine radiopacity similar to that of surrounding dentin. **F**, Three-year radiographic review shows no evident pathological changes apically. The tooth registered normal responses to sensibility testing at both recall periods. (Reprinted with permission, Dr. Till Dammaschke and © Quintessence Deutschland.)



Fig. 24.11 **A**, Bitewing radiograph of quadrants 1 and 4 of an 18-year-old patient displaying a distal carious lesion in the maxillary right second premolar. The patient did not present at the scheduled appointment for restorative care. **B**, The patient returned 4 years later for treatment. Clinical photograph showing iatrogenic pulp exposure at two sites during complete caries excavation. **C**, Photograph of direct capping and base placement with Biodentine (Septodont; St. Maur-des-Fossés, France) applied to the cavity with cement pluggers using light pressure. **D**, Clinical view of cavity restored with bonded composite resin using a two-bottle dentin adhesive. **E**, Radiographic control recorded 4 years after direct capping showing normal periapical tissues. Tooth was asymptomatic with normal response to sensibility testing. (Reprinted with permission, Dr. Till Dammaschke and © Septodont [St. Maur-des-Fossés, France].)

Calcium Silicate Cement Applications in Vital Pulp Therapy

DIRECT PULP CAPPING WITH CALCIUM SILICATE CEMENTS

Controlled prospective investigations on DPC in humans using MTA and other CSCs against cariously exposed pulps are limited but expanding. Collectively, most studies are inconsistent with regard to case selection, treatment strategies, and clinical protocols.²⁶⁸ The spectrum of outcomes reflects the absence of standardized guidelines for caries removal, hemostatic agents, choice and placement of the capping material, and single- versus two-visit delivery sequences. With the advent of quicker setting CSC formulations, indications for two-visit pulp capping are declining in favor of one-visit procedures. Moreover, although the concept of DPC in a carious field is gaining universal acceptance using MTA and other CSCs, clinical recommendations for avoiding and treating pulp exposures in permanent teeth as an accepted management strategy persist, despite contrary evidence.^{129,316} Current international guidelines are variable because the research and technological advances within the field are moving exponentially without a universal consensus.

Human studies using CSCs other than MTA are showing the mutual biocompatibility of new bioceramic materials, indicating that conjointly, the cements exhibit similar properties and cellular responses when exposed to vital pulp tissues. Comparable outcomes are evident when pulp capped teeth are examined for mineralized tissue barrier formation, lack of inflammatory cells, and continued vitality in DPC.^{31,62,181,185,206,211,214,219,243,301} Analysis has shown that initial pulp capping treatment is also cost-effective compared to root canal treatment in younger patients with pulp exposures due to caries.⁶³

Current and past investigations comparing newer CSC formulations have shown clinical and radiographic success in permanent teeth treated with carious exposures ranging from 83.4% to 100% at 1 to 7.4 years.^{31,62,181,185,214,243,244,301} In a larger study using Biodentine as a DPC agent, 245 teeth recalled with an average recall period of 2.3 years showed continued vitality in 86% of the cases. In one study where Biodentine was compared against MTA in a split mouth model or randomly allocated in different patients, outcomes at recall periods of 18 to 36 months were comparable for both materials when examined in permanent mature teeth with carious exposures.²¹⁴ Impressive results have also been demonstrated in several other contemporary studies.^{3,6,238,258} An investigation examined 30 immature permanent teeth exhibiting wide-open apices directly pulp capped with MTA and restored temporarily with intermediate restorative material (IRM).¹³⁸ Definitive permanent composite restorations were placed 2 weeks later, after confirmation of pulp vitality. In these cariously exposed immature permanent teeth, the success rate at a 2-year review was 93%.

One notable factor revealed in a recent study with a broad sample size was that treatment outcomes were negatively influenced when restored with a GIC compared to all other restorative materials.¹⁸¹ The outcome is a likely indicator that GIC should not be considered as a definitive restoration

in DPC cases.¹⁸¹ The outcomes of these current studies strongly suggest that MTA and introduction of new CSC capping agents show capable biocompatibility and sealing properties and can make the outcome of DPC techniques in mature permanent teeth with carious exposures increasingly reliable.

Another observational investigation examined DPC of carious exposures of mature and immature permanent teeth using slow-set MTA in a two-visit sequence.⁵⁶ Forty-nine teeth were examined in patients aged 7 to 45 years over a 1- to 9-year period, with an average 3.94-year observation time. The study protocol used detector dye-aided caries excavation using the DOM, 5.25% to 6% NaOCl hemostasis, bulk MTA placement on pulp exposures, and surrounding dentin, coupled with bonded composite restorations placed at a second visit to compensate for the delayed setting properties of ProRoot MTA. Based on subjective symptomology, cold testing, and radiographic evaluation, 97.96% of teeth showed continued vitality. All patients with immature apices showed continued root formation and apical closure within a 1- to 6-year period (Fig. 24.12).

A related DPC investigation using a two-step protocol in permanent teeth using MTA with bonded restorations with slight variations in procedural execution registered similar outcomes. Sixty-four teeth recalled after 3.6 years showed an overall success rate of 91.3%. The success in patients older than 40 years of age was 80% and for those younger than 40 years was 100%.²⁴⁸ In a corresponding study, 33 patients with DPC after carious exposures and provisionally for 1 week (two-visit protocol) showed a 85% success rate at 3 years.²²⁶ The same study also compared outcomes with patients that received direct CH capping and demonstrated a survival rate of 52% at 3 years. The majority of human studies that compare MTA/CSC direct capping in permanent teeth with CH suggest MTA/CSCs offer more predictable long-term benefits.^{78,226,239} Moreover, larger scale pulp capping studies comparing MTA/CSCs with CH corroborate previous data that demonstrate superior results when MTA/CSCs are applied in a clinical setting (Figs. 24.13 and 24.14).^{66,193,238,260}

The unique physicochemical properties of MTA and CSC also promote a superior environment for pulpal repair and bridge formation, compared to CH products.^{193,238,260,286} MTA and CSC are hygroscopic cements that set in the presence of blood and serum, produce a gap-free interface with dentin, and generate a sustained alkaline pH; in addition, the surface morphology of the hardened cement allows for predictable bonding with current adhesion systems. Growth factors necessary for hard tissue formation are activated by CSCs through the gradual release of calcium ions during curing.²²² The small particle size and alkaline pH contribute to the entombment of remaining cariogenic bacteria at the dentin-MTA and CSC interface, impeding bacterial ingress and caries progression and discouraging continued pulpal injury (Fig. 24.15).^{288,409,414}

PULPOTOMY WITH CALCIUM SILICATE CEMENTS

It has been recommended that pulpectomy be avoided in immature permanent teeth with vital canal tissue so as to protect the remaining radicular pulp tissue and thus encourage continued root development and apexogenesis.^{140,335} Partial




Fig. 24.12 A symptomatic 15-year-old patient presented for treatment with deep caries associated with the maxillary right first molar (#3). **A**, Preoperative radiograph showing deep caries but no evidence of apical pathosis. **B**, Clinical photograph of the carious molar. **C**, Caries removal using caries detector dye. **D**, Clinical view of pulp exposures after 5.25% sodium hypochlorite hemostasis. **E**, Periapical radiograph of direct mineral trioxide aggregate (MTA) pulp cap with wet cotton pellet and unbonded Photocore provisional. **F**, Permanent bonded composite placed 5 days after MTA direct pulp cap. **G**, Clinical photograph of final bonded composite restoration. **H**, Twenty-year 4-month recall radiograph without restorative intervention, patient was asymptomatic and responded normally to cold testing. (Reprinted courtesy Dr. George Bogen with permission.)

pulpotomy to treat direct pulp exposures in immature permanent teeth using CH products has been shown to be a reliable treatment option with proper case selection.^{73,335} However, comparable success rates ranging from 83% to 100% have been demonstrated using CSCs for pulpomies in both immature and mature permanent teeth.^{23,25,39,242,313,361–363,398,399}

Moreover, pulpomies completed with MTA/CSCs do not show complications such as internal resorption, typically seen with CH, formocresol, and ferric sulfate pulpomies (Fig. 24.16).^{126,195,324}

Adult pulpotomy using CSCs is a promising treatment strategy of considerable interest. More important is the




Fig. 24.13 A 23-year-old female patient presented with an IRM temporary restoration placed over a large pulp exposure after caries excavation of the maxillary left second molar (#15). The patient was referred for root canal treatment but had no history of pain and responded normally to sensibility testing. **A**, Periapical radiograph showing temporary material in close proximity to mesial pulp horn. The tooth received a direct pulp cap with mineral trioxide aggregate (MTA) after further caries excavation and 5.25% sodium hypochlorite hemostasis. **B**, Radiograph showing direct MTA (Dentsply, Tulsa Dental, Tulsa, OK) pulp cap and bonded composite restoration placed at second visit. **C**, Two-year 5-month radiograph showing normal periapical structures and newly cemented porcelain onlay. **D**, Periapical radiographic review after 12 years and 8 months. The tooth responded positive to sensibility testing at both recall periods. (© Dr. George Bogen 2019.)

inclusion of symptomatic teeth in clinical investigations that exhibit irreversible pulpitis and show apical radiolucencies consistent with advanced pulp inflammation or partial pulp necrosis.^{23,25,39,242,313,361–363,398,399} The potential for resolution of apical disease in teeth with inflamed pulps displaying apical rarefaction after pulpotomy procedures has been previously documented.^{66,208} One multicentered randomized controlled trial complemented by an earlier study evaluated randomly allocated MTA and CEM adult pulpotomies at 2 and 5 years. The clinical outcomes for both materials were $\geq 98\%$, showing equal effectiveness for both CSCs in permanent molars associated with irreversible pulpitis and apical periodontitis.^{22,24} Another investigation by the same group examined pulpotomy outcomes for CEM measured against conventional orthograde root canal therapy in mature molars diagnosed with irreversible pulpitis. It demonstrated comparable outcomes in pain reduction and the resolution of apical periodontitis, with continued tooth function and survival after 5 years (Fig. 24.17).²³ Both studies showed postoperative pain reduction and the resolution of apical pathosis in the majority of cases. Other investigations have confirmed significant pain reduction in symptomatic permanent teeth with deep caries using CSC pulpotomy.^{152,361} Concurrent studies corroborate findings that pulpotomy treatments performed in mature permanent teeth with irreversible pulpitis and advanced caries using CSCs are a viable future treatment alternative.^{22,23,25,242,361–363}

Indications for pulpotomy have recently transitioned from immature to mature teeth using CSCs, which may improve consumer acceptance and retention rates for patients seeking alternatives to conventional root canal therapy and protective ancillary care. Teeth that present with irreversible pulpitis and experience carious pulp exposures are normally treated with pulpectomy and orthograde root canal treatment coupled with restorative procedures designed to protect the tooth from fracture and microleakage. However, issues with cost effectiveness, holistic concerns, pain management, treatment time, and need for additional appointments when compared to orthograde root canal therapy are strong arguments in favor of this newer treatment option. Pulpotomy in permanent teeth using CSC materials can be recommended as a minimally invasive alternative to traditional root canal treatment.

Vital Pulp Therapy Techniques

DIAGNOSIS

A differential diagnosis based on clinical symptoms and radiographic findings is the aim in assessing pulp vitality. However, an accurate determination of the pulpal condition before treatment initiation is more challenging in younger patients.³⁵⁶ Establishing a diagnosis of reversible versus irreversible pulpitis in immature teeth can be complicated by




Fig. 24.14 A 12-year-old patient presented with a history of pain and cold sensitivity from a mandibular left first molar after having an occlusal composite restoration placed 16 weeks earlier. **A.** Periapical radiograph shows recurrent caries below base of the composite restoration. Note immature apices of the second molar. **B.** Clinical photograph of recently placed occlusal composite restoration. **C.** Photograph of initial caries removal showing remaining decay adjacent to pulpal roof. **D.** Photograph reveals three pulp horn exposures and presence of reparative dentin. **E.** Clinical view of three pulp horn exposures and hemostasis after application of 5% sodium hypochlorite. **F.** Photograph of bulk white mineral trioxide aggregate (MTA) (Pro-Root MTA (Tulsa/Dentsply, Tulsa, OK) placement over exposures and surrounding dentin. The white MTA was covered with a flowable composite and the cavity restored with a bonded composite restoration using a two-bottle bonding system with enamel etching. **G.** One-year periapical radiograph showing normal apical structures. The tooth was asymptomatic and responded positively to vitality testing. (Courtesy Dr. Miguel Marques, Amsterdam, Netherlands.)

subjective symptoms and testing responses that may not accurately reflect pulp histopathology.⁷³ However, efforts should be directed toward the ultimate goal of pulpal preservation and continued apexogenesis in immature permanent teeth.^{53,54} A diagnosis of irreversible pulpitis, based on signs and symptoms, along with clinical testing procedures, does not preclude vital pulp therapy options. Regardless of the treatment choice of pulp capping or partial or complete pulpotomy, preservation of the radicular pulp and apical papilla allows for root maturation in cases of trauma or deep caries.^{146,147,169,342}

Diagnostic quality intraoral radiographs of the involved tooth must be taken to evaluate accurately the extent of root formation and periradicular or furcation changes associated with the periodontal ligament and supporting bone.²⁵⁶ In young permanent teeth, the stage of root development directly influences the diagnosis and treatment options.⁷⁴ Because the faciolingual dimension of most immature roots is greater than the mesiodistal dimension, apical closure may be difficult to determine radiographically.^{74,221} Teeth that demonstrate radiographic evidence of deep caries should not be planned for aggressive procedures, such as pulpectomy, without the benefit of thermal (cold) testing (see Fig. 24.1).

Before arriving at treatment decisions, the clinician should carefully assess all available information; the medical history, patient report, radiographic evidence, clinical evaluation, and vitality (cold) testing are recommended. Periodontal probing, mobility assessment, and the presence of any localized swelling or sinus tracts should be recorded during the evaluation. Radiographs, including bitewings and periapical views, should be evaluated for periapical and furcation pathosis, resorptive defects, and pulpal calcification resulting from trauma or previous restorations.

Patients with deep carious lesions often experience sensitivity to cold, heat, or sweet or acidic foods, and cold tests may evoke a short lingering response of 1 to 2 seconds. This may not be a definitive indicator that the pulp is irreversibly damaged. Determination of the pulpal condition with the aid of contemporary testing methods can be challenging, even for experienced clinicians, because of possible excessive responses to pulp percussion and palpation testing in children.^{148,213,396} Clinical evidence indicates that cold testing with carbon dioxide ice is a more reliable prognosticator of pulp status in immature permanent teeth than electronic testing devices.⁵⁴ However, a diagnosis of irreversible pulpitis or pulp necrosis should be considered for teeth that generate pain on percussion.




Fig. 24.15 Scanning electron micrographs of dentinal tubule obturation by calcium silicate cement (CSC) at the dentin/CSC interface after canals were seeded with *E. faecalis* in phosphate buffered saline (PBS). **A**, Tag formation in dentinal tubules at dentin interface in after application of OrthoMTA (BioMTA, Seoul, Korea) ($\times 35,100$). **B**, Four-week image showing *E. faecalis* entombed by growing crystalline structures within the dentinal tubule ($\times 30,000$). **C**, White arrow shows deformation and damaged cell membrane of *E. faecalis* within an aggregation of leaflet-like and needle-like crystals at 16 weeks ($\times 20,000$). **D**, Sixteen-week specimen showing complete blockage of the dentinal tubule lumen by CSC tight crystalline formation ($\times 20,000$). (Reprinted from Yoo JS, Chang SW, Oh SR, et al: Bacterial entombment by intratubular mineralization following orthograde mineral trioxide aggregate obturation: a scanning electron microscopy study. *Int J Oral Sci* 6:227, 2014, with permission.)




Fig. 24.16 Eleven-year-old female presented 3 hours after trauma with a horizontal crown fracture of the maxillary left central incisor. **A**, Clinical photograph showing midcoronal horizontal fracture. The pulp was exposed and exhibited normal vitality. **B**, Photograph of access cavity after Cvek pulpotomy and placement of gray mineral trioxide aggregate (MTA) (ProRoot MTA, Tulsa/Dentsply, Tulsa, OK). **C**, Photograph of fractured incisal segment before bonding and reattachment. **D**, Six-month radiograph with bonded fractured segment showing initial reparative bridge formation with absence of apical pathosis. The incisor was asymptomatic and responded normally to cold sensibility testing. **E**, Clinical photograph of incisor at 6-month recall. **F**, Eight-year radiographic review. **G**, Eleven-year radiographic recall. Tooth was asymptomatic with normal mobility, probings, and positive response to cold test. (Courtesy Dr. Winston Chee and Dr. Stefan Zweig, Los Angeles, CA.)




Fig. 24.17 Pulpotomy procedures completed for two patients clinically diagnosed with irreversible pulpitis using calcium enriched mixture (CEM) cement (BioniqueDent, Tehran, Iran). **A**, Preoperative radiograph from 27-year-old male patient with deep caries associated with maxillary right quadrant. The first molar was symptomatic with calcified tissue evident in the pulp chamber. **B**, Radiograph after complete pulpotomy using CEM cement restored with bonded composite. **C**, Five-year radiographic recall. The tooth was asymptomatic, firm, with normal probings. **D**, Preoperative radiograph showing deep caries in the mandibular left first (#19) and second (#18) molars in a 41-year-old male patient. Both teeth demonstrated lingering pain to cold testing and tooth #18 was sensitive to percussion. **E**, Postoperative radiograph showing completed miniature pulpotomy #19 and partial pulpotomy #18 after sodium hypochlorite hemostasis and application of CEM cement. Both molars were restored with bonded composites. Tooth #18 demonstrated resolution of symptoms after 24 hours. **F**, Six-year radiographic recall, patient remained asymptomatic and both teeth registered a positive response to sensibility testing. (Courtesy Dr. Saeed Asgary, Tehran, Iran.)

Clinically, the difference between reversible and irreversible pulpitis is often determined on the basis of the duration and intensity of pain.¹⁴⁷ Unprovoked, spontaneous pain of long duration or unrelenting symptoms forcing sleep deprivation are consistent with irreversible pulp inflammation or an acute periapical abscess.⁵⁰ The difficulty in predictably assessing pulpal health and potential degrees of inflammation has been recently addressed in an attempt to improve current terminology that may not accurately reflect pulp conditions during the inflammatory process.⁴⁰¹ It has been proposed that the terms *initial*, *mild*, *moderate*, and *severe pulpitis* be used to replace current terminology for reversible and irreversible pulpitis, better reflecting conditions encountered in the clinical setting. The recategorization of stages of pulpal inflammation attempts to better direct minimally invasive treatment selections using CSCs and is designed to improve outcomes for pulp tissue preservation. However, these assessments can be more complicated than previously proposed, as diagnosed pulp conditions are not always consistent with clinical findings during treatment.^{321,401}

Another consideration in a patient with displacement trauma is transient apical breakdown, which mimics periapical radiolucencies.¹⁶ Teeth that experience luxation-type injuries can discolor and may not respond to cold testing for up to 4 months before they recover normal color and vitality. Also, biologically or pharmacokinetically immunosuppressed patients may not respond to conventional treatments because of abnormal function of related repair mechanisms.^{245,389} Most clinical investigations clearly indicate that

successful outcomes for vital pulp therapy decrease as the patient's age increases. Although aging of the pulp diminishes pulpal volume, vascularity, and host immune responses, functional repair mechanisms can still provide favorable treatment outcomes in older patients (Fig. 24.18).^{1,270}

The initial pulpal diagnosis can be confirmed after visualization of the exposed pulp and assessed during tissue hemostasis. If no hemorrhaging is seen, this area of the tissue is most likely necrotic and must be removed with a high-speed round diamond bur until bleeding is evident (Fig. 24.19). After hemostasis with NaOCl, a large bulk of CSC can be placed directly against the remaining tissue. Alternatively, if hemorrhage control cannot be achieved after 5 to 10 minutes of direct contact with 3% to 6% NaOCl, the pulp is likely to be irreversibly involved, and a full pulpotomy or pulpectomy is recommended.

Although the size of the pulp exposure has no significant bearing on the final outcome, some clinicians falsely assume that larger exposures have an unfavorable prognosis.²⁵² Pulp sizes are underestimated on radiographs.⁸²⁻⁸⁴ The size of the pulp exposures may also be overestimated, which could affect the decision-making process, leading clinicians to abandon more conservative vital pulp treatment options.¹⁶³ Pulp dimensions may also vary between various racial groups and genders.^{83,346,392}

Teeth that have a history of trauma or previous restorations or that display pulpal calcification have a poorer prognosis than teeth showing only initial caries. In the selection of a specific vital pulp treatment, it is important to consider




Fig. 24.18 A 51-year-old patient who presented with a deeply carious but asymptomatic maxillary right first molar. **A**, Preoperative radiograph reveals extensive mesial caries and an occlusal amalgam. **B**, Postoperative radiograph after 1.5 mm pulpal exposure, sodium hypochlorite hemostasis, mineral trioxide aggregate (ProRoot MTA, Tulsa/Dentsply, Tulsa, OK) direct pulp cap, wet cotton pellet placement, and Photocore provisionalization. **C**, Radiograph 1 week after pulp capping and placement of a permanent bonded composite restoration. The patient was asymptomatic and showed a positive response to cold testing. **D**, Six-year radiographic recall; cold testing revealed normal vitality. (© Dr. George Bogen.)




Fig. 24.19 Clinical examples of diseased pulp tissues after sodium hypochlorite hemostasis. **A**, Photograph of exposed pulp tissue of a mandibular right first molar in a 13-year-old patient. Note necrotic pulp tissue (arrows) that was subsequently removed with the remaining coronal pulp during a complete pulpotomy procedure. **B**, Clinical presentation of mandibular right molar in a 7-year-old patient after pulp exposure during caries excavation using a caries detector dye. Note the extruded seminecrotic, nonhemorrhagic tissue (arrow). The tooth later underwent mineral trioxide aggregate partial pulpotomy and permanent restoration. (© Dr. George Bogen.)

the remaining tooth structure and future restorative plan. In patients with uncontrolled caries or extensive loss of coronal structure in which full coverage is indicated, pulpotomy rather than pulp capping is recommended.^{60,73,373}

CARIES REMOVAL

The main objective in caries removal is the identification and complete removal of infected tissue while preserving sound tooth structure; this contributes to pulpal protection and

continued vitality. Caries removal is enhanced with the aid of a caries detector dye and optical magnification; however, it must be understood that dyes can cause excessive and unnecessary removal of healthy tooth structure.^{37,255,408}

Caries removal has traditionally been completed somewhat subjectively using hand instruments and slow-speed burs. The procedure is performed using an explorer and tactile sense to differentiate soft from hard dentin to determine infected from noninfected dental tissue. However, this method has shortcomings because clinicians may leave

decay at the dentinoenamel junction and unnecessarily remove dentin that has the potential to remineralize under a sealed restoration.¹⁴⁹ Furthermore, it has been found that the ability to remove caries varies among operators and during different time periods for the same operator.^{149,150}

Investigators in the early 1970s used SEM to identify two different layers of carious dentin.¹⁵⁰ Teeth show two layers as the result of gram-positive bacteria releasing lactic acid as their main by-product. The outside carious layer subjacent to the enamel-dentin junction exhibited demineralized hydroxyapatite crystals that were dissolved by acidic bacterial by-products; this layer also featured unbound and altered collagen denatured by microbial proteolytic enzymes.³¹² The second demineralized carious layer proximal to the pulp featured degraded hydroxyapatite crystals but contained collagen with intact intermolecular cross links unaffected by cariogenic acids.^{149,150,331} If this deeper layer can be preserved during caries excavation, the remaining pulp tissue and odontoblasts will be subjected to less trauma, contributing to pulpal protection and survival.^{282,326} This layer has a stronger capacity to remineralize when paired with bonded composite restorations to prevent bacterial microleakage.^{269,282}

The two carious layers have been further classified into four zones when analyzed by atomic force microscopy and transverse digital microradiography.³¹² Consistent with previous investigations, the four zones reinforce the concept that increasing levels of demineralization decrease the peritubular dentin rating and mechanical properties of dentin.³¹²

Investigations in human, dog, and nonhuman primate models have demonstrated this regenerative characteristic in caries-affected dentin.^{208,215,269,370,371} Several studies have questioned the efficacy of caries removal using a caries detector dye. Not all stainable dentin can be classified as infected, and the absence of staining does not eliminate the potential for residual cariogenic bacteria.^{218,312} However, dyes allow the operator to visually inspect, with the aid of the DOM, infected dentin that may have been overlooked, particularly at the dentinoenamel junction, where it may compromise treatment outcome.^{218,407} Although a compromise, it may be clinically preferable to inadvertently remove a small excess of dentin than to leave infected tissue.

HEMOSTATIC AGENTS

A wide range of hemostatic solutions and methods have been recommended to control a bleeding pulp exposure. These include various concentrations of NaOCl; 2% CHX; MTAD (Tulsa/Dentsply, Tulsa, OK); 30% hydrogen peroxide (Superoxol); ferric sulfate; disinfectants, such as Tubulicid (Global Dental Products, North Bellmore, NY); epinephrine; direct pressure with cotton pellets soaked in sterile water or saline; and the use of lasers.⁸ NaOCl in concentrations of 1.5% to 5.25% is currently regarded as the most effective, safe, and inexpensive hemostatic solution for pulp capping and partial and complete pulpotomy procedures.^{174,397} First used as a wound antiseptic during World War I and referred to as Dakin's solution, it was soon introduced for root canal irrigation.^{100,104} NaOCl became a valuable hemostatic

agent for direct pulp exposures in the late 1950s.^{173,194,360} The antimicrobial solution provides hemostasis and disinfection of the dentin-pulp interface, chemical amputation of the blood clot and fibrin, biofilm removal, clearance of dentinal chips, and removal of damaged cells at the mechanical exposure site.^{39,126,173,249} Concentrations of 1.5% to 5.25% in direct contact with pulp tissue do not appear to adversely alter pulp cell recruitment, cytodifferentiation, and hard tissue deposition.¹²¹ Rinsing the exposed pulp tissue for 15 minutes with 5 mL NaOCl 5.25% (Clorox) leads to dissolution effects, but these effects are limited to the 3 to 5 upper cell layers without any changes in deeper pulp areas or the dentin. Perfused vital pulp tissue also buffers the chemical activity of NaOCl.³²⁵

An investigation into pulp-capped human third molars treated with either CH or a self-etching adhesive system examined pulps histologically at 30 and 60 days after the use of 2.5% NaOCl for hemostasis.¹³³ Histologic evidence demonstrated no impairment of the repair process after the use of NaOCl, although CH appeared to outperform the resin-based pulp capping agent. Current data clearly support the use of 1.25% to 5.25% NaOCl solutions in humans as a safe and appropriate hemostatic agent for DPC and pulpotomies.^{5,34,121,133,173,192,252,384,388,397}

When pulp exposures occur in a carious field, the ability to attain hemostasis remains the most crucial factor in the success of vital pulp therapy. This was demonstrated in an innovative study that examined outcomes of teeth directly pulp capped with a hard setting CH after exposures were generated during caries excavation.²⁵² Caries removal during the investigation was aided by a caries detector dye with 10% NaOCl for hemostasis. The 2-year success rate was 81.8%. A statistical analysis of key factors revealed that preoperative thermal responses, percussion sensitivity, the diameter of the exposure, the age of the patient, and the tooth type and location had no significant influence on the outcome. The degree of bleeding and its control at the time of exposure constituted the most critical predictor of outcome. When hemostasis can be attained, pulpal repair and reparative dentin formation can proceed normally, in the absence of microbial challenges, when MTA and other CSCs are used as the pulp dressing.^{87,210}

Sodium hypochlorite is an effective hemostatic agent and a valuable tool for assessing the difference between irreversibly and reversibly inflamed pulps as continued hemorrhaging after a 10-minute exposure strongly indicates irreversible pulpitis (Fig. 24.20).

TREATMENT CONSIDERATIONS

An important and often unrecognized aspect of DPC in a carious field is the potential survival of undetected bacteria in tubules adjacent to the exposure site even after caries removal. These microorganisms can compromise treatment even after meticulous excavation and disinfection. Unfortunately, traditional pulp capping protocols have directed clinicians to place pulp dressings only at the exposure site, without considering the adjacent dentin. It is therefore recommended that CSCs be placed over the exposure sites and onto the surrounding dentin to entomb residual microorganisms (see Fig. 24.15).^{409,410}



Fig. 24.20 Thirty-four-year-old female patient presented for root canal treatment with temporary restoration 1 week after caries excavation and pulp exposure of the maxillary right first molar (#3). The patient had mild discomfort and responded with a short lingering pain to cold testing. **A**, Periapical radiograph showing temporary restoration in tooth #3 with normal apical structures. **B**, Photograph of pulpal hemorrhage after temporary removal. **C**, Clinical photograph showing diminished bleeding after 5-minute exposure to 5.25% sodium hypochlorite. **D**, Photograph showing hemorrhage controlled in 10 minutes and 2 mm pulp exposure after continued caries excavation. The exposure and peripheral dentin received bulk OrthoMTA (BioMTA, Seoul, Korea) pulp capping and was covered with a thin wet cotton pellet and provisionalized with Photocore. The tooth was restored permanently with composite resin 1 week later. **E**, Two-year 6-month radiographic follow-up; tooth responded positive to sensibility testing. **F**, Control radiograph at 4 years. Patient exhibited normal pulp testing response and was asymptomatic with normal mobility and probings. (© Dr. George Bogen.)

The concept of biomineralization and bacterial entombment is particularly important when caries removal protocols are ineffective at completely removing undetected acidogenic microorganisms. During the CSC hydration process, calcium-deficient crystalline formation within the dentinal tubules produces bacterial entrapment, entombment, and neutralization.^{409,414} This notable change in pulp capping strategy, based on CSC crystallization properties, can improve treatment outcomes in symptomatic and asymptomatic teeth featuring extensive caries. This includes cavities with multiple exposures after caries excavation or partial and complete pulpotomies when indicated.⁵⁴

Together with an extensive bulk application of MTA/CSC to provide a cement thickness of 1.5 mm or greater, there is an increased likelihood of bacterial neutralization, minimizing further microbial challenges.

A disadvantage of CSCs is their long setting time of up to 228 minutes for ProRoot MTA and up to 85 minutes for Biodentine.²¹⁷ Thus according to the manufacturers' recommendation, CSCs should be allowed to set for a 15-minute minimum (e.g., Biodentine) or 2.5 hours (ProRoot MTA) before a permanent restoration can be placed. Nevertheless, in clinical use waiting even 15 minutes for set can lead to complications. To overcome these

clinical drawbacks and to bypass the long setting time, it has been suggested to cover the MTA or CSC with an RMGI, compomer, or flowable composite resin. The final restoration is then placed allowing the cement to set beneath the interlayer.^{53,75}

Recently it was shown that 3 minutes after mixing MTA or Biodentine, it may be covered with a thin layer of a self-etching, self-bonding flowable composite resin (Vertise flow), an RGMI, or composite resin in combination with a self-etching dentin adhesive. All these restorative materials achieved shear bond strengths to Biodentine or MTA that were similar to those after 15 minutes and 2 days. A longer waiting time after mixing did not increase the adhesion of the lining materials to MTA or Biodentine.³³ Furthermore, the results of previous studies indicated that when placing RMGI on these cements, the time span between the mixing of CSCs and the application of RMGI did not influence the setting reaction of the cement. The moisture of the CSC had no impact on the setting reaction or setting time of RMGI or on the MTA-RMGI structural interface.^{35,131,287} A final permanent restoration can therefore be provided at the same appointment.

Treatment Recommendations[†]

PULP CAPPING AND PULPOTOMY

1. After profound local anesthesia is achieved, the clinical crown is disinfected with NaOCl or CHX after dental dam isolation. Optical magnification and illumination (ideally with a DOM) are highly recommended. The cavity outline is completed using high-speed burs under constant water cooling.
2. Caries excavation is completed using long shank #2-6 round burs in a slow-speed handpiece augmented by hand instrumentation. Removal of caries may be guided by a detector dye if a DOM is used.
3. The cavity and exposure site(s) are immersed with 1.5% to 5.25% NaOCl. Heavy bleeding may be controlled with a cotton pellet moistened with NaOCl under moderate pressure for 5 minutes. If no bleeding is present after the pulp exposure, the area must be examined for necrotic tissue. This is removed with a high-speed round diamond bur under water coolant until bleeding tissue is exposed. Uncontrolled hemorrhaging after 10 minutes can be managed with a full pulpotomy or pulpectomy after assessing the radicular tissue condition. It is CRITICAL that all necrotic tissue is removed (see Fig. 24.19).
4. Prepare MTA or CSC according to the manufacturers' instructions.
5. Using a suitable instrument (composite instrument, Glick #1 endodontic instrument, or MTA carrier gun), apply a large bulk of CSC over the exposure side, including most of the surrounding dentin at a thickness of 1.5 to 3 mm.
6. Remove excess moisture at the site with a dry cotton pellet and leave a clear periphery of dentin for adhesive bonding. A total etch and rinse technique with a phosphoric acid gel is not possible at this stage because the MTA or CSC can be washed away. Either the CSC must show a firm set or a flowable composite/RMGI material must be accurately placed and completely cover the cement.
7. Apply a small amount of a light-curing flowable compomer, an RMGI (or an equivalent light-cured resin-glass ionomer liner), a self-etching, self-bonding flowable composite resin or a flowable composite resin in combination with a self-etching dentin adhesive to cover the CSC and light-cure according to the material's instructions. NOTE: Placement of flowable resins can be more challenging in cases of DPC than indirect pulp capping and pulpotomy procedures.
8. Etch the remaining cavity walls with 34% to 37% phosphoric acid gel for 60 seconds, rinse thoroughly and apply a dentin adhesive (fourth generation, two-bottle systems are highly recommended). Avoid using self-etching dentin adhesives (single-bottle systems).²⁹⁰ Cure according to manufacturers' instructions.
9. Place a composite resin material incrementally as a permanent, final restoration. Light-cure according to manufacturer's instructions.
10. Pulp vitality should be assessed at the next appointment, preferably at 7 to 10 days using a cold test. Radiographic assessment is only needed in case of negative sensibility testing or onset of pain during the first year. Assessments can be made yearly or every 2 years, if indicated.

The Permanent Restoration

A definitive restoration should be provided during the pulp treatment appointment. Temporary restorations over MTA or CSC may lead to significantly lower success rates.^{181,260} It has been reported that teeth which were permanently restored more than 2 days after DPC with MTA exhibited a diminished prognosis.²⁶⁰ The negative impact of the time between DPC and placement of the permanent restoration was also shown for Biodentine and CH.^{110,181} However, if the permanent restoration cannot be placed at the time of definitive pulp treatment due to management concerns, nonbonded translucent core materials such as Photocore (Kuraray Co. Ltd., Osaka, Japan) can provide acceptable protection for extended periods when used in conjunction with CSCs.³⁹

The placement and quality of the permanent restoration can be crucial to the long-term maintenance of pulp vitality and may be more significant than the actual pulp treatment.^{12,142,188,257,264} The aim of the final restoration is to complement the sealing ability of the pulp capping/pulpotomy material and defend the pulp from further microbial challenges. The selection of the restorative material, procedure execution, and adherence to proper restorative protocols can all contribute to minimizing potential restorative

[†]Adapted from Bogen and Chandler.⁵⁵

microleakage. Microleakage around restorations may be more detrimental to vital pulp tissue than unfilled cavity preparations directly exposed to the oral environment.³³⁰ An important consideration in both mature and immature permanent teeth is the conservation of the remaining tooth structure, which ultimately contributes to favorable long-term retention and function.^{93,122,199,351} The incorporation of adhesive restorative materials as definitive final restorations minimizes tooth reduction, encourages anatomic preservation, and thus provides better pulpal protection and repair potential.^{149,172}

Advances in dental materials have increased treatment options in the restoration of teeth that have undergone vital pulp procedures. Permanent restorations for pulp capped or pulp-tomized permanent teeth can include composite resins, bonded or unbonded amalgam restorations, and cuspal coverage restorations. However, the more conservative the restorative treatment, the greater the probability of pulp survival.¹⁴⁹ Vital pulp therapy must be considered an injury to an already challenged connective tissue, and every effort should be directed toward minimizing further injurious procedures.¹ Factors that affect the repair mechanisms in pulp tissue can include the age of the patient, the depth and size of the cavity preparation, and the choice of restorative material.²⁸³

Total etch and self-etching systems produce excellent bond strengths to enamel, dentin, and cured CSCs.^{27,288} The most durable bond strengths generated with contemporary materials are achieved using selective etching of the enamel with 34% to 37% phosphoric acid, followed by two-step, two-bottle, self-etching adhesive systems.^{79,291,387} Current advances in adhesive technology have also shown that beneath the resin-interfused hybrid layer, an acid-base-resistant zone is formed that enhances the resistance of normal dentin to recurrent caries. This reinforced layer forms when monomer penetration and polymerization occur, and it demonstrates an ability to restrict (inhibit) primary and secondary caries.^{290,291} As a result of their simplifications and improved bonding strengths, modern adhesives complement vital pulp therapy. Bonding procedures must strictly follow manufacturers' recommendations and be paired with dental dam placement.⁷⁹

Postoperative Follow-Up and Recall

After treatment completion, the pulp status must be assessed periodically to ensure continued pulp vitality, normal function, and apical closure in immature teeth. Cold testing and radiographic evaluation most accurately assess continued pulp health and are excellent predictors for measuring survival rates. Recalls can address postoperative sensitivity,

pulpal degeneration or necrosis, and indications for further endodontic and restorative care. Review also allows detection of emerging complications such as recurrent caries, poor hygiene, restoration failures, and cuspal fractures.

Patient compliance for recall in asymptomatic cases can be challenging. Because some parents do not practice regular preventive care and may not have a strong background in basic oral health care, recall compliance rates for children can be unpredictable.^{205,311} Although recall has been traditionally based on a 6-month checkup and oral prophylaxis period, this has come into question.²⁶⁵ Recalls can be tailored individually, based on patient need, symptomology, caries indices, periodontal status, and craniofacial development assessment in younger patients.^{292,391}

A tentative diagnosis of tooth survivability can be made at the 3-month recall.²⁵² One study demonstrated that the prognosis for long-term pulp survival can be established at an observation period of 21 to 24 months.²⁵²

Radiographic evidence of root-end closure in immature adult teeth is a reliable prognostic marker of continued pulp vitality (Fig. 24.21).³⁶ Apexogenesis after DPC or pulpotomy procedures using CSCs should proceed normally in healthy patients at a progressive rate.^{39,305,394,400} The observed root maturation should also follow a predictable pattern of tooth development that coincides with the contralateral teeth in the same patient when the teeth are compared radiographically and viewed chronologically.³⁶

Observation of contralateral tooth development can be an invaluable method of measuring the success of vital pulp therapy when using CSCs. Alternatively by comparison, in traumatized teeth that exhibit necrotic pulps and periradicular pathosis, CSCs can be used as an apical plug to stimulate the apical papilla to promote barrier formation, which may require 5 to 20 months for completion (apexification).^{7,90,344} If MTA or another CSC is substituted for CH in vital pulp therapy procedures or apexification, similar time periods for apical maturation or barrier formation can be anticipated (Fig. 24.22).^{132,259,261}

In the absence of microbial challenges, the human dental pulp demonstrates an exceptional regenerative capacity when treated with CSCs independent of patient age. Together with our advances in pulp biology and dental materials, changes in treatment protocols that encourage dental pulp preservation and survival will ultimately contribute to improved dental health for all patients requiring vital pulp therapy.

Acknowledgment

We wish to thank Prof. Dr. Leif K. Bakland and Prof. Dr. Sergio Kuttler for their contributions to this chapter.




Fig. 24.21 An 8-year-old male presented following a traumatic injury to the maxillary left central incisor 2 months earlier. **A**, Periapical radiograph revealed an open apex with a developing radiolucency. The tooth was sensitive to palpation, percussion and negative to cold testing. The diagnosis was necrotic pulp and acute apical periodontitis. **B**, Clinical photograph after access cavity preparation, vital pulp tissue visible coronally. The diagnosis was changed to reversible pulpitis and a partial (Cvek) pulpotomy was performed. **C**, Photograph of white mineral trioxide aggregate (MTA) (ProRoot MTA, Tulsa/Dentsply, Tulsa, OK) applied over the pulp to a thickness of approximately 3 mm. **D**, Radiograph after MTA pulpotomy with provisional restoration. A definitive composite restoration was placed 1 week later. **E**, One-year radiographic recall showing advancing apical closure. **F**, Four-year clinical photograph reveals a slight grey discoloration from the MTA in the cervical area of the tooth. Parents declined option of internal bleaching. **G**, Radiographic review at 9 years reveals apical maturation and thickening of the root walls. The tooth responded positively to cold sensibility testing. (Reprinted courtesy Dr. Marga H. Ree, Purmerend, Netherlands with permission.)




Fig. 24.22 **A**, Preoperative radiograph of a 7-year-old male patient exhibiting a dens evaginatus anatomical anomaly associated with the maxillary right lateral incisor. The parents had been advised to extract the tooth, which was symptomatic and nonresponsive to vitality tests. **B**, A periapical radiograph after cleaning the coronal portion of the canal and irrigation with 2.12% sodium hypochlorite. A coronal plug using ProRoot MTA (Tulsa/Dentsply, Tulsa, OK) was placed and sealed with a provisional restoration. **C**, Four-year radiographic review demonstrates complete root formation with maturation and apical root closure. The tooth was asymptomatic with normal mobility and probings. (Courtesy Dr. Mahmoud Torabinejad.)

References

1. Abou-Rass M: The stressed pulp condition: an endodontic-restorative diagnostic concept, *J Prosthet Dent* 48:264, 1982.
2. About I: Recent trends in tricalcium silicates for vital pulp therapy, *Curr Oral Health Rep* 2018. <https://doi.org/10.1007/s40496-018-0186-y>.
3. Accorinte ML, Loguercio AD, Reis A, et al: Response of human dental pulp capped with MTA and calcium hydroxide powder, *Oper Dent* 33:488, 2008.
4. Accorinte MLR, Loguercio AD, Reis A, et al: Evaluation of two mineral trioxide aggregate compounds as pulp-capping agents in human teeth, *Int Endod J* 42:122, 2009.
5. Accorinte Mde L, Loguercio AD, Reis A, et al: Adverse effects of human pulps after direct pulp capping with different components from a total-etch, three-step adhesive system, *Dent Mater* 21:599, 2005.
6. Aeinehchi M, Eslami B, Ghanberiha M, et al: Mineral trioxide aggregate (MTA) and calcium hydroxide as pulp-capping agents in human teeth: a preliminary report, *Int Endod J* 36:225, 2003.
7. Aggarwal V, Miglani S, Singla M: Conventional apexification and revascularization induced maturogenesis of two non-vital, immature teeth in same patient: 24 months follow up of a case, *J Conserv Dent* 68, 2012.
8. Akashi G, Kato J, Hirai Y: Pathological study of pulp treated with chemicals after Er:YAG laser preparation, *Photomed Laser Surg* 24:698, 2006.
9. Akhlaghi N, Khademi A: Outcomes of vital pulp therapy in permanent teeth with different medicaments based on review of the literature, *Dent Res J (Isfahan)* 12:406, 2015.
10. Al-Hezaimi K, Salameh Z, Al-Fouzan K, et al: Histomorphometric and micro-computed tomography analysis of pulp response to three different pulp capping materials, *J Endod* 37:507, 2011.
11. Alghaithy RA, Qualtrough AJ: Pulp sensibility and vitality tests for diagnosing pulpal health in permanent teeth: a critical review, *Int Endod J* 50:135, 2017.
12. Alpekin T, Ozer F, Unlu N, et al: In vivo and in vitro evaluations of microleakage around Class I amalgam and composite restorations, *Oper Dent* 35:641, 2010.
13. American Academy of Pediatric Dentistry, Clinical Affairs Committee, Pulp Therapy Subcommittee: Guideline on pulp therapy for primary and immature permanent teeth: reference manual 2012-13, *Pediatr Dent* 34:222, 2012.
14. American Association of Endodontists: *Glossary of endodontic terms*, ed 8, Chicago, 2016.
15. Andelin WE, Shabahang S, Wright K, et al: Identification of hard tissue after experimental pulp capping using dentin sialoprotein (DSP) as a marker, *J Endod* 29:646, 2003.
16. Andreasen F: Transient apical breakdown and its relation to color and sensibility changes, *Endod Dent Traumatol* 2:9, 1986.
17. Araújo LB, Cosme-Silva L, Fernandes AP, et al: Effects of mineral trioxide aggregate, Biodentine™ and calcium hydroxide on viability, proliferation, migration and differentiation of stem cells from human exfoliated deciduous teeth, *J Appl Oral Sci* 26:e20160629, 2018.
18. Arruda RA, Cunha RS, Miguita KB, et al: Sealing ability of mineral trioxide aggregate (MTA) combined with distilled water, chlorhexidine, and doxycycline, *J Oral Sci* 54:233, 2012.
19. Arun A, Mythri H, Chachapan D: Pulp vitality tests - an overview on comparison of sensitivity and vitality, *Indian J Oral Sci* 6:41, 2015.
20. Asgary S, Ahmadyar M: Vital pulp therapy using calcium-enriched mixture: an evidence-based review, *J Conserv Dent* 16:92, 2013.
21. Asgary S, Eghbal MJ: Treatment outcomes of pulpotomy in permanent molars with irreversible pulpitis using biomaterials: a multi-center randomized controlled trial, *Acta Odontol Scand* 71:130, 2013.
22. Asgary S, Eghbal MJ, Bagheban AA: Long-term outcomes of pulpotomy in permanent teeth with irreversible pulpitis: a multi-center randomized controlled trial, *Am J Dent* 30:151, 2017.
23. Asgary S, Eghbal MJ, Fazlyab M, et al: Five-year results of vital pulp therapy in permanent molars with irreversible pulpitis: a non-inferiority multicenter randomized clinical trial, *Clin Oral Investig* 19:335, 2015.
24. Asgary S, Eghbal MJ, Ghoddusi J, et al: One-year results of vital pulp therapy in permanent molars with irreversible pulpitis: an ongoing multicenter, randomized, non-inferiority clinical trial, *Clin Oral Investig* 17:431, 2013.
25. Asgary S, Hassanizadeh R, Torabzadeh H, et al: Treatment outcomes of 4 vital pulp therapies in mature molars, *J Endod* 44:529, 2018.
26. Asgary S, Moosavi SH, Yadegari Z, et al: Cytotoxic effect of MTA and CEM cement in human gingival fibroblast cells: scanning electronic microscope evaluation, *N Y State Dent J* 78:51, 2012.
27. Atabek D, Sillelioglu H, Olmez A: Bond strength of adhesive systems to mineral trioxide aggregate with different time intervals, *J Endod* 38:1288, 2012.
28. Atmeh AR, Chong EZ, Richard G: Calcium silicate cement-induced remineralization of totally demineralized dentine in comparison with glass ionomer cement: tetracycline labelling and two-photon fluorescence microscopy, *J Microsc* 257:151, 2015.
29. Atmeh AR, Chong EZ, Richard G, et al: Dentin-cement interfacial interaction: calcium silicates and polyalkenoates, *J Dent Res* 91:454, 2012.
30. Ausschill TM, Arweiler NB, Hellwig E, et al: Success rate of direct pulp capping with calcium hydroxide, *Schweiz Monatsschr Zahnmed* 113:946, 2003.
31. Awawdeh L, Al-Qudah A, Hamouri H, et al: Outcomes of vital pulp therapy using mineral trioxide aggregate or biodentine: a prospective randomized clinical trial, *J Endod* 44:1603, 2018.
32. Awawdeh L, Hemaidat K, Al-Omari W: Higher maximal occlusal bite force in endodontically treated teeth versus vital contralateral counterparts, *J Endod* 43:871, 2017.
33. Babbush CA, Fehrenbach MJ, Emmons M, editors: *Mosby's dental dictionary*, ed 2, St. Louis, 2008, Mosby Elsevier Publishing.
34. Bal C, Alacam A, Tuzuner T, et al: Effects of antiseptics on pulpal healing under calcium hydroxide pulp capping: a pilot study, *Eur J Dent* 5:265, 2011.
35. Ballal S, Venkateshbabu N, Nandini S, et al: An in vitro study to assess the setting and surface crazing of conventional glass ionomer cement when layered over partially set mineral trioxide aggregate, *J Endod* 34:478, 2008.
36. Ballesio I, Marchetti E, Mummolo S, et al: Radiographic appearance of apical closure in apexification: follow-up after 7-13 years, *Eur J Paediatr Dent* 7:29, 2006.
37. Banerjee A, Kidd EA, Watson TF: In vitro validation of carious dentin removed using different excavation criteria, *Am J Dent* 16:228, 2003.
38. Barnes IM, Kidd EA: Disappearing dycal, *Br Dent J* 147:111, 1979.
39. Barrieshi-Nusair KM, Qudeimat MA: A prospective clinical study of mineral trioxide aggregate for partial pulpotomy in cariously exposed permanent teeth, *J Endod* 32:731, 2006.
40. Barthel CR, Rosenkranz B, Leuenberg A, et al: Pulp capping of carious exposures treatment outcome after 5 and 10 years: a retrospective study, *J Endod* 26:525, 2000.
41. Basturk FB, Nekoofer MH, Gunday M, et al: The effect of various mixing and placement techniques on the compressive strength of mineral trioxide aggregate, *J Endod* 39:111, 2013.
42. Baume LJ, Holz J: Long term clinical assessment of direct pulp capping, *Int Endod J* 31:251, 1981.
43. Bergenholtz G: Effect of bacterial products on inflammatory reactions in the dental pulp, *Scand J Dent Res* 85:122, 1977.
44. Bergenholtz G: Evidence for bacterial causation of adverse pulpal responses in resin-based dental restorations, *Crit Rev Oral Biol Med* 11:467, 2000.
45. Berger T, Baratz AZ, Gutmann JL: In vitro investigations into the etiology of mineral trioxide tooth staining, *J Conserv Dent* 17:526, 2014.
46. Bernick S, Nedelman C: Effect of aging on the human pulp, *J Endod* 1:88, 1975.
47. Berzins DW: Chemical properties of MTA. In Torabinejad M, editor: *Mineral trioxide aggregate: properties and clinical applications*, Ames, 2014, Wiley Blackwell Publishing.
48. Bhavana V, Chaitanya KP, Gandhi P, et al: Evaluation of antibacterial and antifungal activity of new calcium-based cement (Biodentine) compared to MTA and glass ionomer cement, *J Conserv Dent* 18:44, 2015.
49. Bimstein E, Rotstein I: Cvek pulpotomy - revisited, *Dent Traumatol* 32:438, 2016.
50. Bjørndal L, Darvann T, Thylstrup A: A quantitative light microscopic study of the odontoblast and subodontoblastic reactions to active and arrested enamel caries without cavitation, *Caries Res* 32:59, 1998.
51. Bjørndal L, Fransson H, Bruun G, et al: Randomized clinical trials on deep carious lesions: 5-year follow-up, *J Dent Res* 96:747, 2017.
52. Bjørndal L, Reit C, Bruun G, et al: Treatment of deep caries lesions in adults: randomized clinical trials comparing stepwise vs direct complete excavation, and direct pulp capping vs partial pulpotomy, *Eur J Oral Sci* 118:290, 2010.
53. Bogen B, Chandler N: Vital pulp therapy. In Ingle J, Bakand L, Baumgartner J, editors: *Ingle's endodontics*, Hamilton, 2008, BC Decker Publishing.
54. Bogen G, Chandler NP: Pulp preservation in immature permanent teeth, *Endod Topics* 23:131, 2012.

55. Bogen G, Chandler NP: Vital pulp therapy. In Rotstein I, Ingle JL, editors: *Ingle's endodontics*, ed 7, Raleigh, 2019, PMPH U.S.A.
56. Bogen G, Kim JS, Bakland LK: Direct pulp capping with mineral trioxide aggregate: an observational study, *J Am Dent Assoc* 139:305, 2008.
57. Bortoluzzi EA, Broon NJ, Bramante CM, et al: Sealing ability of MTA and radiopaque Portland cement with or without calcium chloride for root-end filling, *J Endod* 32:897, 2006.
58. Bortoluzzi EA, Niu LN, Palani CD, et al: Cytotoxicity and osteogenic potential of silicate calcium cements as potential protective materials for pulpal revascularization, *Dent Mater* 31:1510, 2015.
59. Bouillaguet S, Wataha J, Hanks CT, et al: In vitro cytotoxicity and dentin permeability of HEMA (2-hydroxyethyl methacrylate), *J Endod* 22:244–248, 1996.
60. Brambilla E, García-Godoy F, Strohmenger L: Principles of diagnosis and treatment of high-caries-risk subjects, *Dent Clin North Am* 44:507, 2000.
61. Brännström M, Lind PO: Pulpal response to early dental caries, *J Dent Res* 44:1045, 1965.
62. Brizuela C, Ormeño A, Cabrera C, et al: Direct pulp capping with calcium hydroxide, mineral trioxide aggregate, and biodentine in permanent young teeth with caries: a randomized clinical trial, *J Endod* 43:1776, 2017.
63. Brodén J, Davidson T, Fransson H: Cost-effectiveness of pulp capping and root canal treatment of young permanent teeth, *Acta Odontol Scand* 15:1, 2019.
64. Burke FJ, Lucarotti PS: Ten year survival of bridges placed in the general dental services in England and Wales, *J Dent* 40:886, 2012.
65. Byers MR, Taylor PE, Khayat BG, et al: Effects of injury and inflammation on pulpal and periapical nerves, *J Endod* 16:78, 1990.
66. Calişkan MK: Pulpotomy of carious vital teeth with periapical involvement, *Int Endod J* 28:172, 1995.
67. Camargo SE, Camargo CH, Hiller KA, et al: Cytotoxicity and genotoxicity of pulp capping materials in two cell lines, *Int Endod J* 42:227, 2009.
68. Camilleri J: Characterization of hydration products of mineral trioxide aggregate, *Int Endod J* 41:408, 2008.
69. Camilleri J: Color stability of white mineral trioxide aggregate in contact with hypochlorite solution, *J Endod* 40:436, 2014.
70. Camilleri J, Laurent P, About I: Hydration of Biodentine, Theracal LC, and a prototype tricalcium silicate-based dentin replacement material after pulp capping in entire tooth cultures, *J Endod* 40:1846, 2014.
71. Camilleri J, Montesin FE, Brady K, et al: The constitution of mineral trioxide aggregate, *Dent Mater* 21:297, 2005.
72. Camilleri J, Sorrentino F, Damidot D: Investigation of the hydration and bioactivity of radiopacified tricalcium silicate cement, Biodentine and MTA Angelus, *Dent Mater* 29:580, 2013.
73. Camp J: Pediatric endodontic treatment. In Cohen S, Burns RC, editors: *Pathways of the pulp*, ed 7, St. Louis, 1998, Mosby.
74. Camp JH, Fuks AB: Pediatric endodontics: endodontic treatment for the primary and young permanent dentition. In Cohen S, Hargreaves K, editors: *Pathways of the pulp*, ed 9, St. Louis, 2006, Mosby/Elsevier.
75. Cao Y, Bogen G, Lim J, et al: Bioceramic materials and the changing concepts in vital pulp therapy, *J Calif Dent Assoc* 44:278, 2016.
76. Caplan DJ, Cai J, Yin G, et al: Root canal filled versus non-root canal filled teeth: a retrospective comparison of survival times, *J Public Health Dent* 65:90, 2005.
77. Caplan DJ, Kolker J, Rivera EM, et al: Relationship between number of proximal contacts and survival of root treated teeth, *Int Endod J* 35:193, 2002.
78. Caplan DJ, Weintraub JA: Factors related to loss of root canal filled teeth, *J Public Health Dent* 57:31, 1997.
79. Cardoso MV, De Almeida Neves A, et al: Current aspects on bonding effectiveness and stability in adhesive dentistry, *Aust Dent J* 56(Suppl 1):31, 2011.
80. Carlisle EM: Silicon: a possible factor in bone calcification, *Science* 176:279, 1970.
81. Cavalcanti BN, Rode Sde M, Franca CM, et al: Pulp capping materials exert an effect of the secretion of IL-1 β and IL-8 by migrating human neutrophils, *Braz Oral Res* 25:13, 2011.
82. Chandler NP, Ng BP, Monteith BD: Radiographic recognition and distribution of approximal carious lesions in New Zealand undergraduate dental students, *N Z Dent J* 101:106, 2005.
83. Chandler NP, Pitt Ford TR, Monteith BD: Coronal pulp size in molars: a study of bitewing radiographs, *Int Endod J* 36:757, 2003.
84. Chandler NP, Pitt Ford TR, Monteith BD: Pulp size in molars: underestimation on radiographs, *J Oral Rehabil* 31:764, 2004.
85. Charadram N, Austin C, Trimby P, et al: Structural analysis of reactionary dentin formed in response to polymicrobial invasion, *J Struct Biol* 181(3):207–222, 2013.
86. Charadram N, Farahani RM, Harty D, et al: Regulation of reactionary dentin formation by odontoblasts in response to polymicrobial invasion of dentin matrix, *Bone* 50:265, 2012.
87. Cho SY, Seo DG, Lee SJ, et al: Prognostic factors for clinical outcomes according to time after direct pulp capping, *J Endod* 39:327, 2013.
88. Christensen GJ: Pulp capping, *J Am Dent Assoc* 129:1297, 1998.
89. Chueh LH, Chiang CP: Histology of irreversible pulpitis premolars treated with mineral trioxide aggregate pulpotomy, *Oper Dent* 35:370, 2010.
90. Chueh LH, Huang GT: Immature teeth with periradicular periodontitis or abscess undergoing apexogenesis: a paradigm shift, *J Endod* 32:1205, 2006.
91. Ciasca M, Aminoshariae A, Jin G, et al: A comparison of the cytotoxicity and proinflammatory cytokine production of EndoSequence root repair material and ProRoot mineral trioxide aggregate in human osteoblast cell culture using reverse-transcriptase polymerase chain reaction, *J Endod* 38:486, 2012.
92. Cohenca N, Paranjpe A, Berg J: Vital pulp therapy, *Dent Clin North Am* 57:59, 2013.
93. Convery Y LP: Conserving the immature first permanent molar, *J Ir Dent Assoc* 14:76, 1968.
94. Costa CAS, Hebling J, Hanks CT: Current status of pulp capping with dentin adhesive systems: a review, *Dent Mater* 16:188, 2000.
95. Couve E, Osorio R, Schmachtenberg O: The amazing odontoblast: activity, autophagy, and aging, *J Dent Res* 92:765, 2013.
96. Cox CF, Hafez AA, Akimoto N, et al: Biocompatibility of primer, adhesive and resin composite systems on non-exposed and exposed pulps of non-human primate teeth, *Am J Dent* 11: S55, 1998.
97. Cox CF, Keall CL, Keall HJ, et al: Biocompatibility of surface-sealed dental materials against exposed pulps, *J Prosthet Dent* 57:1, 1987.
98. Cox CF, Sübay RK, Ostro E, et al: Tunnel defects in dentinal bridges: their formation following direct pulp capping, *Oper Dent* 21:4, 1996.
99. Cox CF, Suzuki S: Re-evaluating pulp protection: calcium hydroxide liners vs cohesive hybridization, *J Am Dent Assoc* 125:823, 1994.
100. Crane AB: *A practicable root canal technique*, Philadelphia, 1920, Lea & Febiger.
101. Cvek M: A clinical report on partial pulpotomy and capping with calcium hydroxide in permanent incisors with complicated root fractures, *J Endod* 4:232, 1978.
102. Cvek M, Lundberg M: Histological appearance of pulps after exposure by a crown fracture, partial pulpotomy, and clinical diagnosis of healing, *J Endod* 9:8, 1983.
103. de Blanco LP: Treatment of crown fractures with pulp exposure, *Oral Surg Oral Med Oral Pathol Oral Radiol Endod* 82:564, 1996.
104. Dakin HD: On the use of certain antiseptic substances in treatment of infected wounds, *Br Med J* 2:318, 1915.
105. Damas BA, Wheeler MA, Bringas JS, et al: Cytotoxicity comparison of mineral trioxide aggregates and EndoSequence bioceramic root repair materials, *J Endod* 37:372, 2011.
106. Dammaschke T: The formation of reparative dentine and Höhl cells in the dental pulp, *ENDO (Lond Engl)* 4:255, 2010.
107. Dammaschke T: Die indirekte Überkappung der Pulpa, *Quintessenz* 67:1309, 2016.
108. Dammaschke T, Camp JH, Bogen G: MTA in vital pulp therapy. In Torabinejad M, editor: *Mineral trioxide aggregate – properties and clinical applications*, Ames, 2014, Wiley Blackwell Publishing.
109. Dammaschke T, Gerth HUV, Züchner H, et al: Chemical and physical surface and bulk material characterization of white ProRoot MTA and two Portland cements, *Dent Mater* 21:731, 2005.
110. Dammaschke T, Leidinger J, Schäfer E: Long-term evaluation of direct pulp capping: treatment outcomes over an average period of 6.1 years, *Clin Oral Investig* 14:559, 2010.
111. Dammaschke T, Nowicka A, Lipski M, et al: Histological evaluation of hard tissue formation after direct pulp capping with a fast-setting mineral trioxide aggregate (RetroMTA) in humans, *Clin Oral Investig* 2019. doi:1007/s00784-019-02876-2. [Epub ahead of print]
112. Dammaschke T, Stratmann U, Fischer RJ, et al: A histological investigation of direct pulp capping in rodents with dentin adhesives and calcium hydroxide, *Quintessenz Int* 41:e62, 2010.

113. Dammaschke T, Stratmann U, Fischer RJ, et al: Proliferation of rat molar pulp cells after direct pulp capping with dentine adhesive and calcium hydroxide, *Clin Oral Invest* 15:577, 2011.
114. Dammaschke T, Stratmann U, Wolff P, et al: Direct pulp capping with mineral trioxide aggregate: an immunohistologic comparison with calcium hydroxide in rodents, *J Endod* 36:814, 2010.
115. Dammaschke T, Wolff P, Saqheri D, et al: Mineral trioxide aggregate for direct pulp capping: an histologic comparison with calcium hydroxide in rat molars, *Quintessence Int* 41:20, 2010.
116. Darvell BW, Wu RC: "MTA"—an hydraulic silicate cement: review update and setting reaction, *Dent Mater* 27:407, 2011.
117. D'Antò V, Di Caprio MP, Ametrano G, et al: Effect of mineral trioxide aggregate on mesenchymal stem cells, *J Endod* 36:1839, 2010.
118. De Backer H, Van Maele G, Decock V, et al: Long-term survival of complete crowns, fixed dental prostheses, and cantilever prostheses with post and cores on root-canal treated teeth, *Int J Prosthodont* 20:229, 2007.
119. De Mendonça AA, De Oliveira CF, Hebling J, et al: Influence of thicknesses of smear layer on the transdentinal cytotoxicity and bond strength of a resin-modified glass-ionomer cement, *Braz Dent J* 23:379, 2012.
120. Déjou J, Raskin A, Colombani J, et al: Physical, chemical and mechanical behavior of a new material for direct posterior fillings, *Eur Cell Mater* 10(Suppl 4):22, 2005.
121. Demir T, Cehreli ZC: Clinical and radiographic evaluation of adhesive pulp capping in primary molars following hemostasis with 1.25% sodium hypochlorite: 2-year results, *Am J Dent* 20:182, 2007.
122. Dennison JB, Hamilton JC: Treatment decisions and conservation of tooth structure, *Dent Clin North Am* 49:825, 2005.
123. Dettwiler CA, Walter M, Zaugg LK, et al: In vitro assessment of the tooth staining potential of endodontic materials in a bovine tooth model, *Dent Traumatol* 32:480, 2016.
124. Do Nascimento ABL, Fontana UF, Teixeira HM, et al: Biocompatibility of a resin-modified glass-ionomer cement applied as pulp capping in human teeth, *Am J Dent* 13:28, 2000.
125. Domine L, Holz J: [The aging of the human pulp-dentin organ], *Schweiz Monatsschr Zahnmed* 101:725, 1991.
126. Doyle TL, Casas MJ, Kenny DJ, et al: Mineral trioxide aggregate produces superior outcomes in vital primary molar pulpotomy, *Pediatr Dent* 32:41, 2010.
127. Dreger LA, Felipe WT, Reyes-Carmona JF, et al: Mineral trioxide aggregate and Portland cement promote biomineralization in vivo, *J Endod* 38:324, 2012.
128. Duda S, Dammaschke T: Maßnahmen zur Vitalerhaltung der Pulpa. Gibt es Alternativen zum Kalziumhydroxid bei der direkten Überkappung? *Quintessenz* 59:1327, 2008.
129. Duncan HF, Galler KM, Tomson PL, et al: European Society of Endodontology position statement: Management of deep caries and the exposed pulp. *Int Endod J* 2019. doi:10.1111/iej.13080.
130. Eghbal MJ, Asgary S, Baglue RA, et al: MTA pulpotomy of human permanent molars with irreversible pulpitis, *Aust Endod J* 35:4, 2009.
131. Eid AA, Komabayashi T, Watanabe E, et al: Characterization of the mineral trioxide aggregate-resin modified glass ionomer cement interface in different setting conditions, *J Endod* 38:1126, 2012.
132. El-Meligy OA, Avery DR: Comparison of mineral trioxide aggregate and calcium hydroxide as pulpotomy agents in young permanent teeth (apexogenesis), *Pediatr Dent* 28:399, 2006.
133. Elias RV, Demarco FF, Tarquinio SB, et al: Pulp responses to the application of a self-etching adhesive in human pulps after controlling bleeding with sodium hypochlorite, *Quintessence Int* 38:67, 2007.
134. Eskandarizadeh A, Shahpasandzadeh MH, Shahpasandzadeh M, et al: A comparative study on dental pulp response to calcium hydroxide, white and grey mineral trioxide aggregate as pulp capping agents, *J Conserv Dent* 14:351, 2011.
135. European Society of Endodontology: Quality guidelines for endodontic treatment: consensus report of the European Society of Endodontology, *Int Endod J* 39:921, 2006.
136. Farges JC, Alliot-Licht B, Renard E, et al: Dental pulp defence and repair mechanisms in dental caries, *Mediators Inflamm* 2015:230251, 2015. doi:10.1155/2015/230251.
137. Farges JC, Carrouel F, Keller JF, et al: Cytokine production by human odontoblast-like cells upon Toll-like receptor-2 engagement, *Immunobiology* 216:513, 2011.
138. Farsi N, Alamoudi N, Balto K, et al: Clinical assessment of mineral trioxide aggregate (MTA) as direct pulp capping in young permanent teeth, *Pediatr Dent* 31:72, 2006.
139. Fisher FJ, McCabe JF: Calcium hydroxide base materials: an investigation into the relationship between chemical structure and antibacterial properties, *Br Dent J* 144:341, 1978.
140. Fong CD, Davis MJ: Partial pulpotomy for immature permanent teeth, its present and future, *Pediatr Dent* 24:29, 2002.
141. Ford TR, Torabinejad M, Abedi HR, et al: Using mineral trioxide aggregate as a pulp-capping material, *J Am Dent Assoc* 127:1491, 1996.
142. Forss H, Widström E: The post-amalgam era: a selection of materials and their longevity in primary and young permanent dentitions, *Int J Paediatr Dent* 13:158, 2003.
143. Fridland M, Rosado R: MTA solubility: a long term study, *J Endod* 31:376, 2005.
144. Fuks AB: Pulp therapy for the primary and young permanent dentitions, *Dent Clin North Am* 44:571, 2000.
145. Fuks AB, Cosack A, Klein H, et al: Partial pulpotomy as a treatment alternative for exposed pulps in crown-fractured permanent incisors, *Endod Dent Traumatol* 3:100, 1987.
146. Fuks AB, Gavra S, Chosack A: Long-term follow up of traumatized incisors treated by partial pulpotomy, *Pediatr Dent* 15:334, 1993.
147. Fuks AB, Heling I: Pulp therapy for the young permanent dentition. In Pinkham JR, Casamassimo PS, Fields HW, et al, editors: *Pediatric dentistry: infancy through adolescence*, ed 24, St. Louis, 2005, Saunders/Elsevier.
148. Fulling HJ, Andreasen JO: Influence of maturation status and tooth type of permanent teeth upon electrometric and thermal pulp testing procedures, *Scand J Dent Res* 84:286, 1976.
149. Fusayama T: *A simple pain-free adhesive restorative system by minimal reduction and total etching*, St. Louis, 1993, Ishiyaku Euro America Publishing.
150. Fusayama T, Kurosaki N: Structure and removal of carious dentin, *Int Dent J* 22:401, 1972.
151. Fuss Z, Lustig J, Katz A, et al: An evaluation of endodontically treated vertical root fractured teeth: impact of operative procedures, *J Endod* 27:46, 2001.
152. Galani M, Tewari S, Sangwan P, et al: Comparative evaluation of postoperative pain and success rate after pulpotomy and root canal treatment in cariously exposed mature permanent molars: a randomized controlled trial, *J Endod* 43:1953, 2017.
153. Gandolfi MG, Ciapetti G, Taddei P, et al: Apatite formation on bioactive calcium-silicate cements for dentistry affects surface topography and human marrow stromal cells proliferation, *Dent Mater* 26:974, 2010.
154. Gandolfi MG, Siboni F, Prati C: Chemical-physical properties of TheraCal, a novel light-curable MTA-like material for pulp capping, *Int Endod J* 45:571, 2012.
155. Gandolfi MG, van Lunduyt K, Taddei P, et al: Environmental scanning electron microscopy connected with energy dispersive X-ray analysis and Raman techniques to study ProRoot mineral trioxide aggregate and calcium silicate cements in wet conditions and in real time, *J Endod* 36:851, 2010.
156. Goldberg M: Reactionary and reparative dentin-like structures, In Goldberg M, editor: *The dental pulp – biology, pathology, and regenerative therapies*, Berlin, 2014, Springer-Verlag.
157. Goldberg M: The pulp reaction beneath the carious lesion. In Goldberg M, editor: *Understanding dental caries*, Berlin, 2016, Springer-Verlag.
158. Goldberg M, Farges JC, Lacerda-Pinheiro S, et al: Inflammatory and immunological aspects of dental pulp repair, *Pharmacol Res* 58:137, 2008.
159. Goldberg M, Lasfargues JJ, Legrand JM: Clinical testing of dental materials—histological considerations, *Dent J* 22:S25, 1994.
160. Gonçalves JL, Viapiana R, Miranda CE, et al: Evaluation of physico-chemical properties of Portland cements and MTA, *Braz Oral Res* 24:277, 2010.
161. Goodis HE, Kahn A, Simon S: Aging and the pulp. In: Hargreaves K, Goodis HE, Tay F, editors: *Seltzer and Bender's dental pulp*, ed 2, Hanover Park, 2012, Quintessence Publishing.
162. Goracci G, Mori G: Scanning electron microscopic evaluation of resin-dentin and calcium hydroxide dentin-interface with resin composite restorations, *Quintessence Int* 27:129, 1996.
163. Gracia TB: *Accuracy of size estimations by dentists of simulated pulp exposures and cavity preparations*. MDS (endodontics) research report, Dunedin, New Zealand, 2006, University of Otago.

164. Graham L, Cooper PR, Cassidy N, et al: The effect of calcium hydroxide on solubilisation of bioactive dentine matrix components, *Biomaterials* 27:2865, 2006.
165. Granath LE, Hagman G: Experimental pulpotomy in human bicusps with reference to cutting technique, *Acta Odontol Scand* 29:155, 1971.
166. Grech L, Mallia B, Camilleri J: Characterization of set intermediate restorative material, Biodentine, Bioaggregate and a prototype calcium silicate cement for use as root-end filling materials, *Int Endod J* 46:632, 2012.
167. Grötz KA, Duschner H, Reichert TE, et al: Histotomography of the odontoblast processes at the dentine-enamel junction of permanent healthy human teeth in the confocal laser scanning microscope, *Clin Oral Investig* 2:21, 1998.
168. Gudkina J, Mindere A, Locane G, et al: Review of the success of pulp exposure treatment of cariously and traumatically exposed pulps in immature permanent incisors and molars, *Stomatologija* 14:71, 2012.
169. Gutmann JL, Heaton JF: Management of the open (immature) apex. Part 1. Vital teeth, *Int Endod J* 14:166, 1981.
170. Guven EP, Yalvac ME, Sahin F, et al: Effect of calcium hydroxide-containing cement, mineral trioxide aggregate, and enamel matrix derivative on proliferation and differentiation of human tooth germ stem cells, *J Endod* 37:650, 2011.
171. Guven G, Cehreli ZC, Ural A, et al: Effect of mineral trioxide aggregate cements on transforming growth factor beta-1 and bone morphogenetic protein production by human fibroblasts in vitro, *J Endod* 33:447, 2007.
172. Gwinnett J, Tay FR, Pang KM, et al: Quantitative contribution of collagen network in dentin hybridization, *Am J Dent* 9:140, 1996.
173. Hafez AA, Cox CF, Tarim B, et al: An in vivo evaluation of hemorrhage control using sodium hypochlorite and direct capping with a one- or two-component adhesive system in exposed nonhuman primate pulps, *Quintessence Int* 33:261, 2002.
174. Haghighi R, Abbasi F: A histopathological comparison of pulpotomy with sodium hypochlorite and formocresol, *Iran Endod J* 7:60, 2012.
175. Hahn CL, Liewehr FR: Innate immune responses of the dental pulp to caries, *J Endod* 33:643, 2007.
176. Hahn CL, Liewehr FR: Relationships between caries bacteria, host responses, and clinical signs and symptoms of pulpitis, *J Endod* 33:213, 2007.
177. Hahn CL, Liewehr FR: Update on the adaptive immune responses of the dental pulp, *J Endod* 33:773, 2007.
178. Ham KA, Witherspoon DE, Gutmann JL, et al: Preliminary evaluation of BMP-2 expression and histological characteristics during apexification with calcium hydroxide and mineral trioxide aggregate, *J Endod* 31:275, 2005.
179. Han L, Okiji T: Uptake of calcium and silicon released from calcium silicate-based endodontic materials into root canal dentine, *Int Endod J* 44:1081, 2011.
180. Hanks CT, Strawn SE, Wataha JC, et al: Cytotoxic effects of resin components on cultured mammalian fibroblasts, *J Dent Res* 70:1450, 1991.
181. Harms CS, Schäfer E, Dammaschke T: Clinical evaluation of direct pulp capping using a calcium silicate cement - treatment outcomes over an average period of 2.3 years, *Clin Oral Investig* 2018. doi:10.1007/s00784-018-2767-5.
182. Hashem D, Mannocci F, Patel S, et al: Clinical and radiographic assessment of the efficacy of calcium silicate indirect pulp capping: a randomized controlled clinical trial, *J Dent Res* 94:562, 2015.
183. Hebling J, Giro EMA, DeSouza Costa CA: Biocompatibility of an adhesive system applied to exposed human dental pulp, *J Endod* 25:676, 1999.
184. Hebling J, Lessa FC, Nogueira I, et al: Cytotoxicity of resin-based light-cured liners, *Am J Dent* 22:137, 2009.
185. Hegde S, Sowmya B, Mathew S, et al: Clinical evaluation of mineral trioxide aggregate and biodentine as direct pulp capping agents in carious teeth, *J Conserv Dent* 20:91, 2017.
186. Helfer AR, Melnick S, Schilder H: Determination of the moisture content of vital and pulpless teeth, *Oral Surg Oral Med Oral Pathol* 34:661, 1972.
187. Henderson B, Wilson M: Cytokine induction by bacteria: beyond lipopolysaccharide, *Cytokine* 8:269, 1996.
188. Henderson HZ, Setcos JC: The sealed composite resin restoration, *ASDC J Dent Child* 52:300, 1985.
189. Hermann B: Ein weiterer Beitrag zur Frage der Pulpenbehandlung, *Zahnärztl Rundsch* 37:1327, 1928.
190. Hessle CC, Andersson B, Wold AE: Gram-positive and gram-negative bacteria elicit different patterns of pro-inflammatory cytokines in human monocytes, *Cytokine* 30:311, 2005.
191. Higashi T, Higashi T, Okamoto H: Characteristics and effects of calcified degenerative zones on the formation of hard tissue barriers in amputated canine dental pulp, *J Endod* 22:168, 1996.
192. Hilton TJ: Keys to clinical success with pulp capping: a review of the literature, *Oper Dent* 34:615, 2008.
193. Hilton TJ, Ferracane JL, Mancl L, Northwest Practice-based Research Collaborative in Evidence-based Dentistry (NWP): Comparison of CaOH with MTA for direct pulp capping: a PBRN randomized clinical trial, *J Dent Res* 92:16S, 2013.
194. Hirota K: A study on the partial pulp removal (pulpotomy) using four different tissue solvents, *J Jpn Stomatol Soc* 26:1588, 1959.
195. Holan G, Eidelman E, Fuks A: Long-term evaluation of pulpotomy in primary molars using mineral trioxide aggregate or formocresol, *Pediatr Dent* 27:129, 2005.
196. Horsted P, Sondergaard B, Thylstrup A, et al: A retrospective study of direct pulp capping with calcium hydroxide compounds, *Endod Dent Traumatol* 1:29, 1985.
197. Hörsted-Bindslev P, Vilkinis V, Sidlauskas A: Direct capping of human pulps with a dentin bonding system or with calcium hydroxide cement, *Oral Surg Oral Med Oral Pathol Oral Radiol Endod* 96:591, 2003.
198. Hörsted-Bindslev P, Bergenholtz G: Vital pulp therapies. In Bergenholtz G, Hörsted-Bindslev P, Erik-Reit C, editors: *Textbook of endodontology*, Oxford, 2003, Blackwell Munksgaard Publishing.
199. Hosoda H, Fusayama T: A tooth substance saving restorative technique, *Int Dent J* 34:1, 1984.
200. Inokoshi S, Iwaku M, Fusayama T: Pulpal response to a new adhesive resin material, *J Dent Res* 61:1014, 1982.
201. Ishizaka R, Hayashi Y, Iohara K, et al: Stimulation of angiogenesis, neurogenesis and regeneration by side population cells from dental pulp, *Biomaterials* 34:1888, 2013.
202. Issa Y, Watts DC, Brunton PA, et al: Resin composite monomers alter MTT and LDH activity of human gingival fibroblasts in vitro, *Dent Mater* 20:12, 2004.
203. Izumi T, Kobayashi I, Okamura K, et al: Immunohistochemical study on the immunocompetent cells of the pulp in human non-carious and carious teeth, *Arch Oral Biol* 40:609, 1995.
204. Jameson MW, Hood JAA, Tidmarsh BG: The effects of dehydration and rehydration on some mechanical properties of human dentine, *J Biomech* 26:1055, 1993.
205. Jamieson WJ, Vargas K: Recall rates and caries experience of patients undergoing general anesthesia for dental treatment, *Pediatr Dent* 29:253, 2007.
206. Jang Y, Song M, Yoo IS, et al: A randomized controlled study of the use of ProRoot mineral trioxide aggregate and endocem as direct pulp capping materials: 3-months versus 1-year outcome, *J Endod* 41:1201, 2015.
207. Jontell M, Hanks CT, Bratel J, et al: Effects of unpolymerized resin components on the function of accessory cells derived from the rat incisor pulp, *J Dent Res* 74:1162, 1995.
208. Jordan RE, Suzuki M: Conservative treatment of deep carious lesions, *J Can Dent Assoc* 37:337, 1971.
209. Jung S, Mielert J, Kleinheinz J, et al: Human oral cells' response to different endodontic restorative materials: an in vitro study, *Head Face Med* 10:55, 2014. doi:10.1186/s13005-014-0055-4.
210. Kakehashi S, Stanley HR, Fitzgerald RT: The effects of surgical exposures of dental pulps in germ-free and conventional laboratory rats, *Oral Surg Oral Med Oral Pathol* 20:340, 1965.
211. Kang CM, Sun Y, Song JS, et al: A randomized controlled trial of various MTA materials for partial pulpotomy in permanent teeth, *J Dent* 60:8, 2017.
212. Kangarlou A, Sofiabadi S, Asgari S, et al: Assessment of antifungal activity of ProRoot mineral trioxide aggregate and mineral trioxide aggregate-Angelus, *Dent Res J (Isfahan)* 9:256, 2012.
213. Karibe H, Ohide Y, Kohno H, et al: Study on thermal pulp testing of immature permanent teeth, *Shigaku* 77:1006, 1989.
214. Katge FA, Patil DP: Comparative analysis of 2 calcium silicate-based cements (biodentine and mineral trioxide aggregate) as direct pulp-capping agent in young permanent molars. A split mouth study, *J Endod* 43:507, 2017.

215. Kato S, Fusayama T: Recalcification of artificially decalcified dentin in vivo, *J Dent Res* 49:1060, 1970.
216. Kaup M, Dammann CH, Schäfer E, et al: Shear bond strength of Biodentine, ProRoot MTA, glass ionomer cement and composite resin on human dentine ex vivo, *Head Face Med* 11:14, 2015.
217. Kaup M, Schäfer E, Dammanschke T: An in vitro study of different material properties of Biodentine compared to ProRoot MTA, *Head Face Med* 11:16, 2015.
218. Kidd EA, Ricketts DN, Beighton D: Criteria for caries removal at the enamel-dentine junction: a clinical and microbiological study, *Br Dent J* 180:287, 1996.
219. Kim RJ, Kim MO, Lee KS, et al: An in vitro evaluation of the antibacterial properties of three mineral trioxide aggregate (MTA) against five oral bacteria, *Arch Oral Biol* 60:1497, 2015.
220. Kim S, Heyeraas KJ, Haug SR: Structure and function of the dentin-pulp complex. In Ingle JJ, Bakand LK, Baumgartner JC, editors: *Ingle's endodontics*, ed 6, Hamilton, Ontario, 2008, Decker.
221. Kim YJ, Chandler NP: Determination of working length for teeth with wide or immature apices: a review, *Int Endod J* 46:483, 2013.
222. Koh ET, Pitt Ford TR, Torabinejad M, et al: Mineral trioxide aggregate stimulates cytokine production in human osteoblasts, *J Bone Min Res* 10S:S406, 1995.
223. Koh ET, Torabinejad M, Pitt Ford TR, et al: Mineral trioxide aggregate stimulates a biological response in human osteoblasts, *J Biomed Mater Res* 37:432, 1997.
224. Krastl G, Allgayer N, Lenherr P, et al: Tooth discoloration induced by endodontic materials: a literature review, *Dent Traumatol* 29:2, 2013.
225. Krastl G, Weiger R: Vital pulp therapy after trauma, *Endod Pract Today* 8:293, 2014.
226. Kundzina R, Stangvaltaite L, Eriksen HM, et al: Capping carious exposures in adults: a randomized controlled trial investigating mineral trioxide aggregate versus calcium hydroxide, *Int Endod J* 50:924, 2017.
227. Kuratate M, Yoshida K, Shigetani Y, et al: Immunohistochemical analysis of nestin, osteopontin, and proliferating cells in the reparative process of exposed dental pulp capped with mineral trioxide aggregate, *J Endod* 34:970, 2008.
228. Luttler Y: Classification of dentin into primary, secondary and tertiary, *Oral Surg Oral Med Oral Pathol* 12:996, 1959.
229. Langeland K: Management of the inflamed pulp associated with deep carious lesion, *J Endod* 7:169, 1981.
230. Lasfargues JJ, Machtou P: Collège National des Enseignants en Odontologie Conservatrice et Endodontie (CNEOC). Dictionnaire Francophone des termes d'Odontologie Conservatrice. *Endodontie & Odontologie restauratrice*, 2ème édition, Espace id, 2010.
231. Laurent P, Camps J, About I: Biodentine™ induces TGF- β 1 release from human pulp cells and early dental pulp mineralization, *Int Endod J* 45:439, 2012.
232. Laurent P, Camps J, De Méo M, et al: Induction of specific cell responses to a Ca(3)SiO(5)-based posterior restorative material, *Dent Mater J* 24:1486, 2008.
233. Lee YH, Kim GE, Cho HJ, et al: Aging of in vitro pulp illustrates change of inflammation and dentinogenesis, *J Endod* 39:340, 2013.
234. Lenherr P, Allgayer N, Weiger R, et al: Tooth discoloration induced by endodontic materials: a laboratory study, *Int Endod J* 45:942, 2012.
235. Lertchirakarn V, Palamara JE, Messer HH: Patterns of vertical root fracture: factors affecting stress distribution in the root canal, *J Endod* 29:523, 2003.
236. Lesot H, Bègue-Kirn C, Kubler MD, et al: Experimental induction of odontoblast differentiation and stimulation during reparative processes, *Cells Mater* 3:201, 1993.
237. Lessa FC, Aranha AM, Hebling J, et al: Cytotoxic effects of white MTA and MTA-Bio cements on odontoblast-like cells (MDPC-23), *Braz Dent J* 21:24, 2010.
238. Leye Benoist F, Gaye Ndiaye F, Kane AW, et al: Evaluation of mineral trioxide aggregate (MTA) versus calcium hydroxide cement (Dycal) in the formation of a dentine bridge: a randomised controlled trial, *Int Dent J* 62:33, 2012.
239. Li Z, Cao L, Fan M, et al: Direct pulp capping with calcium hydroxide or mineral trioxide aggregate: a meta-analysis, *J Endod* 41:1412, 2015.
240. Lin LM, Rosenberg PA: Repair and regeneration in endodontics, *Int Endod J* 44:889, 2011.
241. Linn J, Messer HH: Effect of restorative procedures on the strength of endodontically treated molars, *J Endod* 20:479, 1994.
242. Linsuwanont P, Wimonutthikul K, Pothimoke U, et al: Treatment outcomes of mineral trioxide aggregate pulpotomy in vital permanent teeth with carious pulp exposure: the retrospective study, *J Endod* 43:225, 2017.
243. Linu S, Lekshmi MS, Varunkumar VS, et al: Treatment outcome following direct pulp capping using bioceramic materials in mature permanent teeth with carious exposure: a pilot retrospective study, *J Endod* 43:1635, 2017.
244. Lipski M, Nowicka A, Kot K, et al: Factors affecting the outcomes of direct pulp capping using Biodentine, *Clin Oral Investig* 22:2021, 2018.
245. Mahmoud SH, Mel-A, Zaher AR, et al: Influence of selective immunosuppressive drugs on the healing of exposed dogs' dental pulp capped with mineral trioxide aggregate, *J Endod* 36:95, 2010.
246. Mantellini MG, Botero TM, Yaman P, et al: Adhesive resin induces apoptosis and cell-cycle arrest of pulp cells, *J Dent Res* 82:592, 2003.
247. Marchi JJ, De Araujo FB, Fröner AM, et al: Indirect pulp capping in the primary dentition: a 4 year follow-up study, *J Clin Pediatr Dent* 31:68, 2006.
248. Marques MS, Wesselink PR, Shemesh H: Outcome of direct pulp capping with mineral trioxide aggregate, *J Endod* 41:1026, 2015.
249. Mass E, Zilberman U: Long-term radiologic pulp evaluation after partial pulpotomy in young permanent molars, *Quintessence Int* 42:547, 2011.
250. Mathieu S, Jeanneau C, Sheibat-Othman N, et al: Usefulness of controlled release of growth factors in investigating the early events of dentin-pulp regeneration, *J Endod* 39:228, 2013.
251. Matsumoto S, Hayashi M, Suzuki Y, et al: Calcium ions released from mineral trioxide aggregate convert the differentiation pathway of C2C12 cells into osteoblast lineage, *J Endod* 39:68, 2013.
252. Matsuo T, Nakanishi T, Shimizu H, et al: A clinical study of direct pulp capping applied to carious-exposed pulps, *J Endod* 22:551, 1996.
253. Matsuura T, Katsumata T, Matsuura T, et al: Histopathological study of pulpal irritation of dental adhesive resin. Part 1. Panavia EX, *Nihon Hotetsu Shika Gakkai Zasshi* 31:104, 1987.
254. Matysiak M, Dubois JP, Ducastelle T, et al: Morphometric analysis of human pulp myelinated fibers during aging, *J Biol Buccale* 14:69, 1986.
255. McComb D: Caries-detector dyes: how accurate and useful are they? *J Can Dent Assoc* 66:195, 2000.
256. McDonald RE, Avery DR, Dean JA: Treatment of deep caries, vital pulp exposure, and pulpless teeth. In Dean JA, Avery DR, McDonald RE, editors: *McDonald and Avery's dentistry of the child and adolescent*, ed 9, St. Louis, 2011, Mosby/Elsevier.
257. Memarpour M, Mesbahi M, Shafiei F: Three-and-a-half-year clinical evaluation of posterior composite resin in children, *J Dent Child* 77:92, 2010.
258. Mente J, Geletnek B, Ohle M, et al: Mineral trioxide aggregate or calcium hydroxide direct pulp capping: an analysis of the clinical treatment outcome, *J Endod* 36:806, 2010.
259. Mente J, Hage N, Pfeiffer T, et al: Mineral trioxide aggregate apical plugs in teeth with open apical foramina: a retrospective analysis of treatment outcome, *J Endod* 35:1354, 2009.
260. Mente J, Hufnagel S, Leo M et al. Treatment of mineral trioxide aggregate or calcium hydroxide direct pulp capping: long-term results, *J Endod* 40:1746, 2014.
261. Mente J, Leo M, Panagidis D, et al: Treatment outcome of mineral trioxide aggregate in open apex teeth, *J Endod* 39:20, 2013.
262. Mentink AG, Meeuwissen R, Käyser AF, et al: Survival rate and failure characteristics of the all metal post and core restoration, *J Oral Rehabil* 20:455, 1993.
263. Merdad K, Sonbul H, Bukhary S, et al: Caries susceptibility of endodontically versus nonendodontically treated teeth, *J Endod* 37:139, 2011.
264. Mertz-Fairhurst EJ, Call-Smith KM, Shuster GS, et al: Clinical performance of sealed composite restorations placed over caries compared with sealed and unsealed amalgam restorations, *J Am Dent Assoc* 115:689, 1987.
265. Mettes D: Insufficient evidence to support or refute the need for 6-monthly dental check-ups: What is the optimal recall frequency between dental checks? *Evid Based Dent* 6:62, 2005.
266. Min KS, Park HJ, Lee SK, et al: Effect of mineral trioxide aggregate on dentin bridge formation and expression of dentin sialoprotein and heme oxygenase-1 in human pulp, *J Endod* 34:666, 2008.

267. Minamikawa H, Yamada M, Deyama Y, et al: Effect of N-acetylcysteine on rat dental pulp cells cultured on mineral trioxide aggregate, *J Endod* 37:637, 2011.
268. Miyashita H, Worthington HV, Qualtrough A, et al: Pulp management for caries in adults: maintaining pulp vitality, *Cochrane Database Syst Rev* 18:CD004484, 2007.
269. Miyauchi H, Iwaku M, Fusayama T: Physiological recalcification of carious dentin, *Bull Tokyo Med Dent Univ* 25:169, 1978.
270. Mjör IA: Pulp-dentin biology in restorative dentistry. Part 5: Clinical management and tissue changes associated with wear and trauma, *Quintessence Int* 32:771, 2001.
271. Mjör IA: Pulp-dentin biology in restorative dentistry. Part 7: The exposed pulp, *Quintessence Int* 33:113, 2002.
272. Modena KC, Casas-Apayco LC, Atta MT, et al: Cytotoxicity and biocompatibility of direct and indirect pulp capping materials, *J Appl Oral Sci* 17:544, 2009.
273. Moghaddame-Jafari S, Mantellini MG, Botero TM, et al: Effect of ProRoot MTA on pulp cell apoptosis and proliferation in vitro, *J Endod* 31:387, 2005.
274. Mohammadi Z, Dummer PMH: Properties and applications of calcium hydroxide in endodontics and dental traumatology, *Int Endod J* 44:697, 2011.
275. Moretti AB, Sakai VT, Oliveira TM, et al: The effectiveness of mineral trioxide aggregate, calcium hydroxide and formocresol for pulpotomies in primary teeth, *Int Endod J* 41:547, 2008.
276. Morse DR: Age-related changes of the dental pulp complex and their relationship to systemic aging, *Oral Surg Oral Med Oral Pathol* 72:721, 1991.
277. Morse DR, Esposito JV, Schoor RS: A radiographic study of aging changes of the dental pulp and dentin in normal teeth, *Quintessence Int* 24:329, 1993.
278. Mozayeni MA, Milani AS, Marvasti LA, et al: Cytotoxicity of calcium enriched mixture cement compared with mineral trioxide aggregate and intermediate restorative material, *Aust Dent J* 38:70, 2012.
279. Mozyńska J, Metlerski M, Lipski M, et al: Tooth discoloration induced by different calcium silicate-based cements. A systematic review of in vitro studies, *J Endod* 43:1593, 2017.
280. Mudie AS, Holland GR: Local opioids in the inflamed dental pulp, *J Endod* 32:319, 2006.
281. Murray PE, About I, Lumley PJ, et al: Cavity remaining dentin thickness and pulpal activity, *Am J Dent* 15:41, 2002.
282. Murray PE, Hafez AA, Smith AJ, et al: Histomorphometric analysis of odontoblast-like cell numbers and dentine bridge secretory activity following pulp exposure, *Int Endod J* 36:106, 2003.
283. Murray PE, Smith AJ: Saving pulps: a biological basis—an overview, *Prim Dent Care* 9:21, 2002.
284. Murray PE, Smith AJ, Windsor LJ, et al: Remaining dentine thickness and human pulp responses, *Int Endod J* 36:33, 2003.
285. Murray PE, Stanley HR, Matthews JB, et al: Age-related odontometric changes of human teeth, *Oral Surg Oral Med Oral Pathol Oral Radiol Endod* 93:474, 2002.
286. Nair PNR, Duncan HF, Pitt Ford TR, et al: Histological, ultrastructural and quantitative investigations on the response of healthy human pulps to experimental pulp capping with mineral trioxide aggregate: a randomized controlled trial, *Int Endod J* 41:128, 2008.
287. Nandini S, Ballal S, Kandaswamy D: Influence of glass-ionomer cement on the interface and setting reaction of mineral trioxide aggregate when used as a furcal repair material using laser Raman spectroscopic analysis, *J Endod* 33:167, 2007.
288. Neelakantan P, Grotra D, Subbarao CV, et al: The shear bond strength of resin-based composite to white mineral trioxide aggregate, *J Am Dent Assoc* 143:e40, 2012.
289. Ng YL, Mann V, Gulabivala K: A prospective study of the factors affecting outcomes of non-surgical root canal treatment. Part 2. Tooth survival, *Int Endod J* 44:610, 2011.
290. Nikaido T, Nurrohmah H, Takagaki T, et al: Nanoleakage in hybrid layer and acid-base resistant zone at the adhesive/dentin interface, *Microsc Microanal* 21:1271, 2015.
291. Nikaido T, Weerasinghe DD, Waidyasekera K, et al: Assessment of the nanostructure of acid-base resistant zone by the application of all-in-one adhesive systems: super dentin formation, *Biomed Mater Eng* 19:163, 2009.
292. Nikiforuk G: Optimal recall intervals in child dental care, *J Can Dent Assoc* 63:618, 1997.
293. Nissan R, Segal H, Pashley D, et al: Ability of bacterial endotoxin to diffuse through human dentin, *J Endod* 21:62, 1995.
294. Nosrat A, Seifi A, Asgary S: Pulpotomy in caries-exposed immature permanent molars using calcium-enriched mixture cement or mineral trioxide aggregate: a randomized clinical trial, *Int J Paediatr Dent* 23:56, 2013.
295. Nowicka A, Lipski M, Parafiniuk M, et al: Response of human dental pulp capped with Biodentine and mineral trioxide aggregate, *J Endod* 39:743, 2013.
296. Nowicka A, Parafiniuk M, Lipski M, et al: Pulpodentin complex response after direct capping with self-etch adhesive systems, *Folia Histochem Cytobiol* 50:565, 2012.
297. Nowicka A, Wilk G, Lipski M, et al: Tomographic evaluation of reparative dentin formation after direct pulp capping with Ca(OH)₂, MTA, Biodentine, and dentin bonding system in human teeth, *J Endod* 41:1234, 2015.
298. Okiji T, Yoshida K: Reparative dentinogenesis induced by mineral trioxide aggregate: a review from the biological and physicochemical points of view, *Int J Dent* 46:280, 2009.
299. Paranjpe A, Smoot T, Zhang H, et al: Direct contact with mineral trioxide aggregate activates and differentiates human dental pulp cells, *J Endod* 37:1691, 2011.
300. Paranjpe A, Zhang H, Johnson JD: Effects of mineral trioxide aggregate on human pulp cells after pulp-capping procedures, *J Endod* 36:1042, 2010.
301. Parinyaprom N, Nirunsittirat A, Chuveera P, et al: Outcomes of direct pulp capping by using either ProRoot Mineral Trioxide Aggregate or Biodentine in permanent teeth with carious pulp exposure in 6- to 18-year-old patients: a randomized controlled trial, *J Endod* 44:341, 2018.
302. Parirokh M, Torabinejad M, Dummer PMH: Mineral trioxide aggregate and other bioactive endodontic cements: an updated overview - part I: vital pulp therapy, *Int Endod J* 51:177, 2018.
303. Park JW, Hong SH, Kim JH, et al: X-ray diffraction analysis of white ProRoot MTA and Diadent BioAggregate, *Oral Surg Oral Med Oral Pathol Oral Radiol Endod* 109:155, 2010.
304. Patel N, Best SM, Bonfield W, et al: A comparative study on the in vivo behavior of hydroxyapatite and silicon substituted hydroxyapatite granules, *J Mater Sci Mater Med* 13:1199, 2002.
305. Patel R, Cohenca N: Maturation of a cariously exposed immature permanent tooth using MTA for direct pulp capping: a case report, *Dent Traumatol* 22:328, 2006.
306. Paterson RC, Watts A: Further studies on the exposed germ-free dental pulp, *Int Endod J* 20:112, 1987.
307. Pedano MS, Li X, Li S, et al: Freshly mixed and setting calcium-silicate cements stimulate human dental pulp cells, *Dent Mater* 34:797, 2018.
308. Pfaff P: *Abhandlung von den Zähnen des menschlichen Körpers und deren Krankheiten*, Berlin, 1756, Haude und Spener.
309. Poggio C, Arciola CR, Beltrami R, et al: Cytocompatibility and antibacterial properties of capping materials, *Sci World J* 2014:181945, 2014.
310. Poggio C, Ceci M, Dagna A, et al: In vitro cytotoxicity evaluation of different pulp capping materials: a comparative study, *Arh Hig Rada Toksikol* 66:181, 2015.
311. Primosch RE, Balsewich CM, Thomas CW: Outcomes assessment an intervention strategy to improve parental compliance to follow-up evaluations after treatment of early childhood caries using general anesthesia in a medicaid population, *ASDC J Dent Child* 68:102, 2001.
312. Pugach MK, Strother J, Darling CL, et al: Dentin caries zones: mineral, structure, and properties, *J Dent Res* 88:71, 2009.
313. Qudeimat MA, Barrieshi-Nusair KM, Owais AI: Calcium hydroxide vs mineral trioxide aggregates for partial pulpotomy of permanent molars with deep caries, *Eur Arch Paediatr Dent* 8:99, 2007.
314. Randow K, Glantz PO: On cantilever loading of vital and non-vital teeth: an experimental clinical study, *Acta Odontol Scand* 44:271, 1986.
315. Ranly DM, Garcia-Godoy F: Current and potential pulp therapies for primary and young permanent teeth, *Dent J* 28:153, 2000.
316. Rebel HH: Über die Ausheilung der freigelegten Pulpa, *Dtsch Zahnheilkd*; 55:3, 1922.
317. Reyes-Carmona JF, Santos AR, Figueiredo CP, et al: In vivo host interactions with mineral trioxide aggregate and calcium hydroxide: inflammatory molecular signaling assessment, *J Endod* 37:1225, 2011.

318. Reyes-Carmona JF, Santos AS, Figueiredo CP, et al: Host-mineral trioxide aggregate inflammatory molecular signaling and biomineralization ability, *J Endod* 36:1347, 2010.
319. Ricucci D, Loghin S, Lin LM, et al: Is hard tissue formation in the dental pulp after the death of the primary odontoblasts a regenerative or a reparative process? *J Dent* 42:1156, 2014.
320. Ricucci D, Loghin S, Niu LN, et al: Changes in the radicular pulp-dentine complex in healthy intact teeth and in response to deep caries or restorations: a histological and histobacteriological study, *J Dent* 73:76, 2018.
321. Ricucci D, Loghin S, Siqueira JF, et al: Correlation between clinical and histologic pulp diagnoses, *J Endod* 40:1932, 2014.
322. Ricucci D, Siqueira JF Jr: Vital pulp therapy. In Ricucci D, Siqueira JF Jr, editors: *Endodontology – an integrated biological and clinical view*, London, 2013, Quintessence Publishing.
323. Rodd HD, Boissonade FM: Comparative immunohistochemical analysis of the peptidergic innervation of human primary and permanent tooth pulp, *Arch Oral Biol* 47:375, 2002.
324. Rölling I, Hasselgren G, Tronstad L: Morphologic and enzyme histochemical observations on the pulp of human primary molars 3 to 5 years after formocresol treatment, *Oral Surg Oral Med Oral Pathol* 42:518, 1976.
325. Rosenfeld EF, James GA, Burch BS: Vital pulp tissue response to sodium hypochlorite, *J Endod* 4:140, 1978.
326. Roth KK, Müller M, Ahrens G: Staining of carious dentin with Kariesdetektor, *Dtsch Zahnärztl Z* 44:460, 1989.
327. Saito T, Toyooka H, Ito S, et al: In vitro study of remineralization of dentin: effects of ions on mineral induction by decalcified dentin matrix, *Caries Res* 37:445, 2003.
328. Salvi GE, Siegrist Guldener BE, Amstad T, et al: Clinical evaluation of root filled teeth restored with or without post-and-core systems in a specialist practice setting, *Int Endod J* 40:209, 2007.
329. Sarkar NK, Caicedo R, Ritwik P, et al: Physiochemical basis of the biologic properties of mineral trioxide aggregate, *J Endod* 31:97, 2005.
330. Sasafuchi Y, Otsuki M, Inokoshi S, et al: The effects on pulp tissue of microleakage in resin composite restorations, *J Med Dent Sci* 46:155, 1999.
331. Sato Y, Fusayama T: Removal of dentin guided by Fuchsin staining, *J Dent Res* 55:678, 1976.
332. Schäfer E, Hickel R, Geurtsen W, et al: Offizielles Endodontologisches Lexikon – mit einem Anhang für Materialien und Instrumente – der Deutschen Gesellschaft für Zahnerhaltung, *Endodontie* 9:129, 2000.
333. Schmidt A, Schäfer E, Dammaschke T: Shear bond strength of lining materials to calcium silicate cements at different time intervals, *J Adhes Dent* 19:129, 2017.
334. Schröder U: Effect of calcium hydroxide-containing pulp capping agents on pulp cell migration, proliferation, and differentiation, *J Dent Res* 66:1166, 1985.
335. Schröder U: Pedodontic endodontics. In Koch G, Poulsen S, editors: *Pediatric dentistry: a clinical approach*, Copenhagen, 2001, Munksgaard.
336. Schroeder HE. *Orale Strukturbiologie*. 3. Aufl. Stuttgart, 1987, Thieme Verlag.
337. Schuur AH, Gruythuysen RJ, Wesselink PR: Pulp capping with adhesive resin-based composite vs. calcium hydroxide: a review, *Endod Dent Traumatol* 16:240, 2000.
338. Schwendicke F: Contemporary concepts in carious tissue removal: a review, *J Esthet Restor Dent* 29:403, 2017.
339. Schwendicke F, Stolpe M: Direct pulp capping after a carious exposure versus root canal treatment: a cost-effectiveness analysis, *J Endod* 40:1764, 2014.
340. Seo MS, Hwang KG, Lee J, et al: The effect of mineral trioxide aggregate on odontogenic differentiation in dental pulp stem cells, *J Endod* 39:242, 2013.
341. Setbon HM, Devaux J, Iserentant A, et al: Influence of composition on setting kinetics of new injectable and/or fast setting tricalcium silicate cements, *Dent Mater* 30:1291, 2014.
342. Shabahang S, Torabinejad M: Treatment of teeth with open apices using mineral trioxide aggregate, *Pract Periodontics Aesthet Dent* 12:315, 2000.
343. Shayegan A, Jurysta C, Atash R, et al: Biodentine used as a pulp-capping agent in primary pig teeth, *Pediatr Dent* 34:202, 2012.
344. Sheehy EC, Roberts GJ: Use of calcium hydroxide for apical barrier formation and healing in non-vital immature permanent teeth: a review, *Br Dent J* 183:241, 1997.
345. Shiba H, Nakanishi K, Rashid F, et al: Proliferative ability and alkaline phosphatase activity with in vivo cellular aging in human pulp cells, *J Endod* 29:9, 2003.
346. Shields ED, Altschuller B, Choi EY, et al: Odontometric variation among American black, European, and Mongoloid populations, *J Craniofac Genet Dev Biol* 10:7, 1990.
347. Shokouhinejad N, Nekoofar MH, Pirmoazen S, et al: Evaluation and comparison of occurrence of tooth discoloration after the application of various calcium silicate-based cements: an ex vivo study, *J Endod* 42:140, 2016.
348. Sigal MJ, Pitaru S, Aubin JE, et al: A combined scanning electron microscopy and immunofluorescence study demonstrating that the odontoblast process extends to the dentinoenamel junction in human teeth, *Anat Rec* 210:453, 1984.
349. Silva GA, Gava E, Lanza LD, et al: Subclinical failures of direct pulp capping of human teeth by using a dentin bonding system, *J Endod* 39:182, 2013.
350. Simon S, Smith AJ, Berdal A, et al: The MAP kinase pathway is involved in odontoblast stimulation via p38 phosphorylation, *J Endod* 36:256, 2010.
351. Simonsen RJ: Conservation of tooth structure in restorative dentistry, *Quintessence Int* 16:15, 1985.
352. Sloan AJ, Perry H, Matthews JB, Smith AJ: Transforming growth factor-beta isoform expression in mature human healthy and carious molar teeth, *Histochem J* 32:247, 2000.
353. Smith AJ: Formation and repair of dentin in the adult. In Hargreaves KM, Goodis HE, Tay FR, editors: *Seltzer and Bender's dental pulp*, ed 2, Chicago, 2012, Quintessence Publishing.
354. Smith AJ, Cassidy N, Perry H, et al: Reactionary dentinogenesis, *Int J Dev Biol* 39:273, 1995.
355. Song JS, Mante FK, Romanow WJ, et al: Chemical analysis of powder and set forms of Portland cement, gray ProRoot MTA, white ProRoot MTA, and gray MTA-Angelus, *Oral Surg Oral Med Oral Pathol Oral Radiol Endod* 102:809, 2006.
356. Souza RA, Gomes SC, Dantas Jda C, et al: Importance of the diagnosis in the pulpotomy of immature permanent teeth, *Braz Dent J* 18:244, 2007.
357. Staehle HJ, Pioch T: Zur alkalisierenden Wirkung von kalziumhaltigen Präparaten, *Dtsch Zahnärztl Z* 43:308, 1988.
358. Stanley HR: Pulp capping—conserving the dental pulp: Can it be done? Is it worth it? *Oral Surg Oral Med Oral Pathol* 68:628, 1989.
359. Subramaniam P, Konde S, Prashanth P: An in vitro evaluation of pH variations in calcium hydroxide liners, *J Indian Soc Pedod Prev Dent* 24:144, 2006.
360. Sudo C: A study on partial pulp removal (pulpotomy) using NaOCl (sodium hypochlorite), *J Jpn Stomatol Soc* 26:1012, 1959.
361. Taha NA, Abdeukhader SZ: Outcome of full pulpotomy using Biodentine in adult patients with symptoms indicative of irreversible pulpitis, *Int Endod J* 51:819, 2018.
362. Taha NA, Abdulkhader SZ: Full pulpotomy with biodentine in symptomatic young permanent teeth with carious exposure, *J Endod* 44:932, 2018.
363. Taha NA, Ahmad MB, Ghanim A: Assessment of mineral trioxide aggregate pulpotomy in mature permanent teeth with carious exposures, *Int Endod J* 50:117, 2017.
364. Taha NA, Khazali MA: Partial pulpotomy in mature permanent teeth with clinical signs indicative of irreversible pulpitis: a randomized clinical trial, *J Endod* 43:1417, 2017.
365. Takita T, Hayashi M, Takeichi O, et al: Effect of mineral trioxide aggregate on proliferation of cultured human dental pulp cells, *Int Endod J* 39:415, 2006.
366. Tang W, Wu Y, Smales RJ: Identifying and reducing risks for potential fractures in endodontically treated teeth, *J Endod* 36:609, 2010.
367. Tarim B, Hafez AA, Cox CF: Pulpal response to a resin-modified glass-ionomer material on nonexposed and exposed monkey pulps, *Quintessence Int* 29:535, 1998.
368. Tarim B, Hafez AA, Suzuki SH, et al: Biocompatibility of compomer restorative systems on nonexposed dental pulps of primate teeth, *Oper Dent* 22:149, 1997.
369. Tarim B, Hafez AA, Suzuki SH, et al: Biocompatibility of Optibond and XR-Bond adhesive systems in nonhuman primate teeth, *Int J Periodontics Restorative Dent* 18:86, 1998.
370. Tatsumi T: Physiological remineralization of artificially decalcified monkey dentin under adhesive composite resin restoration, *Kokubyo Gakkai Zasshi* 56:47, 1989.

371. Tatsumi T, Inokoshi S, Yamada T, et al: Remineralization of etched dentin, *J Prosthet Dent* 67:617, 1992.
372. Ten Cate AR: Dentin-pulp complex. In *Oral histology*, ed 4, St. Louis, 1994, Mosby.
373. Tinanoff N, Douglass JM: Clinical decision making for caries management in children, *Pediatr Dent* 24:386, 2002.
374. Tomson PL, Grover LM, Lumley PJ, et al: Dissolution of bio-active dentine matrix components by mineral trioxide aggregate, *Dent J* 35:636, 2007.
375. Tomson PL, Lumley PJ, Alexander MY, et al: Hepatocyte growth factor is sequestered in dentine matrix and promotes regeneration-associated events in dental pulp cells, *Cytokine* 61:622, 2013.
376. Tønder KJ: Vascular reactions in the dental pulp during inflammation, *Acta Odontol Scand* 41:247, 1983.
377. Torabinejad M, Higa RK, McKendry DJ, et al: Dye leakage of four root end filling materials: effects of blood contamination, *J Endod* 20:159, 1994.
378. Torabinejad M, Parirokh M: Mineral trioxide aggregate: a comprehensive literature review - Part II: leakage and biocompatibility investigations, *J Endod* 36:190, 2010.
379. Torabinejad M, Smith PW, Kettering JD, et al: Comparative investigation of marginal adaptation of mineral trioxide aggregate and other commonly used root-end filling materials, *J Endod* 21:295, 1995.
380. Torbjörner A, Karlsson S, Odman PA: Survival rate and failure characteristics for two post designs, *J Prosthet Dent* 73:439, 1995.
381. Tranasi M, Sberna MT, Zizzari V, et al: Microarray evaluation of age-related changes in human dental pulp, *J Endod* 35:1211, 2009.
382. Tronstad L, Mjör IA: Capping of the inflamed pulp, *Oral Surg Oral Med Oral Pathol* 34:477, 1972.
383. Tuna EB, Dincel ME, Gençay K, et al: Fracture resistance of immature teeth filled with Bioaggregate, mineral trioxide aggregate and calcium hydroxide, *Dent Traumatol* 27:174, 2011.
384. Tüzüner T, Alacam A, Altunbas DA, et al: Clinical and radiographic outcomes of direct pulp capping therapy in primary molar teeth following haemostasis with various antiseptics: a randomised controlled trial, *Eur J Paediatr Dent* 13:289, 2012.
385. Tziafas D, Pantelidou O, Alvanou A, et al: The dentinogenic effect of mineral trioxide aggregate (MTA) in short-term capping experiments, *Int Endod J* 35:245, 2002.
386. Uesrichai N, Nirunsittirat A, Chuveera P, et al: Partial pulpotomy with two bioactive cements in permanent teeth of 6- to 18-year-old patients with signs and symptoms indicative of irreversible pulpitis: a noninferiority randomized controlled trial, *Int Endod J* 2019. doi:10.1111/iej.13071. [Epub ahead of print].
387. Van Meerbeek B, Peumans M, Poitevin A, et al: Relationship between bond-strength tests and clinical outcomes, *Dent Mater* 26:e100, 2010.
388. Vargas KG, Packham B, Lowman D: Preliminary evaluation of sodium hypochlorite for pulpotomies in primary molars, *Pediatr Dent* 28:511, 2006.
389. Wang CH, Chueh LH, Chen SC, et al: Impact of diabetes mellitus, hypertension, and coronary artery disease on tooth extraction after nonsurgical endodontic treatment, *J Endod* 37:1, 2011.
390. Wang G, Wang C, Qin M: Pulp prognosis following conservative pulp treatment in teeth with complicated crown fractures - a retrospective study, *Dent Traumatol* 33:255, 2017.
391. Wang NJ, Aspelund GØ: Preventive care and recall intervals: targeting of services in child dental care in Norway, *Community Dent Health* 27:5, 2010.
392. Wang Y, Zheng QH, Zhou XD, et al: Evaluation of the root and canal morphology of mandibular first permanent molars in a western Chinese population by cone-beam computed tomography, *J Endod* 36:1786, 2010.
393. Wegner PK, Freitag S, Kern M: Survival rate of endodontically treated teeth with posts after prosthetic restoration, *J Endod* 32:928, 2006.
394. Weisleder R, Benitez CR: Maturogenesis: Is it a new concept? *J Endod* 29:776, 2003.
395. Willershausen B, Willershausen I, Ross A, et al: Retrospective study on direct pulp capping with calcium hydroxide, *Quintessence Int* 42:165, 2011.
396. Winters J, Cameron AC, Widmer RP: Pulp therapy for primary and immature permanent teeth. In Cameron AC, Widmer RP, editors: *Handbook of pediatric dentistry*, ed 3, Philadelphia, 2008, Mosby/Elsevier.
397. Witherspoon DE: Vital pulp therapy with new materials: new directions and treatment perspectives—permanent teeth, *J Endod* 34:S25, 2008.
398. Witherspoon DE, Regan JD, Small JC: MTA pulpotomies: a long-term case series outcomes assessment of complicated crown fractures, *Tex Dent J* 134:166, 2017.
399. Witherspoon DE, Small JC, Harris GZ: Mineral trioxide aggregate pulpotomies: a case series outcomes assessment, *J Am Dent Assoc* 137:610, 2006.
400. Witherspoon DE, Small JC, Regan JD, et al: Retrospective analysis of open apex teeth obturated with mineral trioxide aggregate, *J Endod* 34:1171, 2008.
401. Wolters WJ, Duncan HF, Tomson PL, et al: Minimally invasive endodontics: a new diagnostic system for assessing pulpitis and subsequent treatment needs, *Int Endod J* 50:825, 2017.
402. Yalcin M, Arsalin U, Dundar A: Evaluation of antibacterial effects of pulp capping agents with direct contact test method, *Eur J Dent* 8:95, 2014.
403. Yamada T, Nakamura K, Iwaku M, et al: The extent of the odontoblast process in normal and carious human dentin, *J Dent Res* 62:798, 1983.
404. Yamani T, Yamashita A, Takeshita N, et al: Histopathological evaluation of the effects of a new dental adhesive resin on dog dental pulps, *J Jpn Prosthet Soc* 30:671, 1986.
405. Yan P, Yuan Z, Jiang H, et al: Effect of bioaggregate on differentiation of human periodontal ligament fibroblasts, *Int Endod J* 43:1116, 2010.
406. Yasuda Y, Ogawa M, Arakawa T, et al: The effect of mineral trioxide aggregate on the mineralization ability of rat dental pulp cells: an in vitro study, *J Endod* 34:1057, 2008.
407. Yazici AR, Baseren M, Gokalp S: The in vitro performance of laser fluorescence and caries-detector dye for detecting residual carious dentin during tooth preparation, *Quintessence Int* 36:417, 2005.
408. Yip HK, Stevenson AG, Beeley JA: The specificity of caries detector dyes in cavity preparation, *Br Dent J* 176:417, 1994.
409. Yoo JS, Chang SW, Oh SR, et al: Bacterial entombment by intratubular mineralization following orthograde mineral trioxide aggregate obturation: a scanning electron microscopy study, *Int J Oral Sci* 6:227, 2014.
410. Yoo YJ, Baek SH, Kum KY, et al: Dynamic intratubular biomineralization following root canal obturation with pozzolan-based mineral trioxide aggregate sealer cement, *Scanning* 38:50, 2016.
411. Yoshimura A, Lien E, Ingalls RR, et al: Cutting edge: recognition of gram-positive bacterial cell wall components by the innate immune system occurs via toll-like receptor 2, *J Immunol* 163:1, 1999.
412. Yuan Z, Peng B, Jiang H, et al: Effect of bioaggregate on mineral-associated gene expression in osteoblast cells, *J Endod* 36:1145, 2010.
413. Zanini M, Sautier JM, Berdal A, et al: Biodentine induces immortalized murine pulp cell differentiation into odontoblast-like cells and stimulates biomineralization, *J Endod* 38:1220, 2012.
414. Zhang H, Pappen FG, Haapasalo M: Dentin enhances the antibacterial affect of mineral trioxide aggregate, *J Endod* 35:221, 2009.
415. Zias J, Numeroff K: Operative dentistry in the second century BCE, *J Am Dent Assoc* 114:665, 1987.
416. Zoufan K, Jiang J, Komabayashi T, et al: Cytotoxicity evaluation of gutta flow and endo sequence BC sealers, *Oral Surg Oral Med Oral Pathol Oral Radiol Endod* 112:657, 2011.